

HAAKER

EQUIPMENT COMPANY

SINCE 1972



December 10, 2024

Arturo Alvarez
Fresno, City of
5607 West Jenson Ave
Fresno, CA 93706

Thank you for your interest in the RoverX main line inspection system with capabilities to inspect from 6" to 35" pipes. I am pleased to submit the following proposal for your consideration and approval Based on [Sourcewell Cooperative Purchasing Agreement- 120721-EVS.](#)

Proposal for Three (3) High Definition EnviroSight Rover X Pipeline Inspection Systems.



<u>Description</u>	<u>Price:</u>
<u>HD Rover X Package (Qty3):</u>	\$287,720.34
<u>HD RCX90 Zoom Camera:</u> High-Definition CCD color zoom camera with 10x optical and 12x digital zoom, auto shutter, auto/manual focus, built-in LED lighting, +/-135 degree tilt, endless 360 degree rotation, pressure sensor, and twin laser diodes for measuring feature.	

2070 North White Avenue, La Verne, California 91750
(909) 598-2706 ~ FAX (909) 598-1427 ~ haaker.com

HAAKER

EQUIPMENT COMPANY

SINCE 1972

<u>HD ROVVER X 130 Crawler;</u> Steerable with twin high-performance motors and 6-wheel drive, anodized aluminum/stainless steel chassis with pressure indicator, inclination and tilt sensors, location transmitter, rear viewing video camera. Wheels; 6 small rubber wheels, 4 medium rubber wheels, 4 large rubber wheels, 4 wheel spacers and all necessary hardware.	
<u>VC500 Control Pendant;</u> To operate crawler, reel and camera, daylight viewable touch screen, HD-video recording, and desk mount dock.	
<u>HD RAX300 automatic motorized cable reel;</u> With meter counter, splash-proof rating, 1000' orange transmission cable; power supply	
for 115/230V; wireless remote control (for equipment set up); 25' extension cable (connecting VC500 to RAX300) with emergency power switch.	
<u>Pressurization Kit;</u> Regulator, air valve, and two (2) CO2 Canisters, for replacing air into camera, crawler, and accessories. Crawler lowering tool and tool kit.	
ROVVER X Accessories.	
Aluminum Top Manhole Cable Roller (cable protection, sits across manhole). (Qty3)	\$1,463.76
Flexible Cable Guide Pulley (cable protection at pipe beginning). (Qty3)	\$5,336.64
Sub Total:	\$294,520.74
Sales Tax 8.35%:	\$24,592.48
Freight:	\$1,200.00
Equipment Training:	Included
Total Price:	\$320,313.22

We appreciate the opportunity to present this proposal and look forward to being of further and continued service.

Sincerely,

Jorge (George) Lopez
Jorge (George) Lopez