
Site Plan



Building Areas (Approx.)

HSR Station: 165k sf Ped. Bridge: 32ksf Historic Depot: 26ksf Pullman Shed: 13ksf

Day 1 Cross Section



Community Based Organization (CBO) Workshops

Workshop Goals:

Building community partnerships with a focus on mobility, activation and placemaking in and around the future stations. Explore partnership opportunities for projects and grants.

- » 65 CBOs invited: warm up calls, emails, outreach
- » 33 CBO participants attended workshop

Next Steps: "Thank You" messaging & HSR Updates, Identifying Emerging Themes, Potential Projects, Grants Opportunities & further outreach follow up.






CBO Participants

- Aly Tawflik (Fresno State Transportation Institute)
- Andres Jauregui (Gazarian Real Estate Center)
- Anthony Molina (Fresno County Bicycle Coalition)
- Arianna Chavez (Arte Americas)
- Barbara Wilson (Transform Fresno Outreach & Oversight)
- Blake Konczar (Workforce Connection)
- Cody Laird (Fresno County EDC)
- Edgar Olivera (Centro La Familia)
- Elaine Martell (Chinatown Fresno Foundation)
- Elliott Balch (Fresno Downtown Association)
- Eric Martinez (Fresno Arts Council)
- Esther Carver (Lowell CDC)
- Ivan Paz (Every Neighborhood Partnership)
- Jay Minami (Chinatown Fresno Foundation)
- Jordan Sanchez (City of Fresno)
- Joseph Verduzco (Fresno County EDC)
- Kiel Lopez-Schmidt (South Tower Community Land Trust)
- Laura Gromis (USGBC + ATAC)

- Lilia G Chavez (Fresno Arts Council)
- Margarita Rocha (Centro La Familia Advocacy)
- Marianne Kast (League of Women Voters of Fresno)
- Matthew Jendian (CSU Fresno, Humanix)
- Melissa Perry (Generation Changers)
- Mike Osegueda (Fresno Street Eats)
- Mona N Cummings (Tree Fresno)
- Morgan Dolzaki (Chinatown Fresno Foundation & Central Fish)
- Nasreen Johnson (SCCD & Caglia Environmental)
- Nora Monaco (Brewery District LP & Downtown Partnership)
- Renatta Cater-Ford (Property Owner in Fresno)
- Rowell Reyes (DFPC Downtown Fresno Partnership)
- Scott Miller (Fresno Chamber of Commerce + Gazebo Garden + Measure P Commission)
- Tate Hill (Access Plus Capital)
- Tony Heredia (Vendor Village, Fresno Street Eats, 559 Night Market)

Collaborative Workshop





CITY OF FRESNO PRESENTATION MARCH 25, 2024



AGENDA

- 1. High Speed Rail Authority Update
- 2. RAISE Grant Scope and Schedule
- 3. Historic Fresno Station Renovation
 - Project Team
 - Historic Status
 - Construction Chronology and Significance Diagrams
 - Pre-Design Investigative Work
 - Basis of Design



HIGH SPEED RAIL AUTHORITY UPDATE

- 119 miles between Madera and Wasco under active construction
- 52 miles under advanced design (north into Merced and south into Bakersfield)
- Federal grants awarded in 2023:
 - \$3.1 Billion in Federal-State Partnership for Intercity Passenger Rail
 - \$202 Million CRISI grant for grade separations in Shafter
 - \$20 Million RAISE grant for Fresno Historic Deport Renovation
- Created 13,000 construction jobs; 820 Small Businesses on HSR
- Track to Operational Service:
 - Committed to an aggressive goal to have passenger service between Merced and Bakersfield between 2030 and 2033.
 - By the end of 2025, complete all environmental documents for the entire 500-mile system connecting San Francisco and Anaheim.
 - By 2028, complete and begin train testing on the first 119-mile, double-tracked and electrified high-speed rail test track between Madera and Poplar Avenue.
 - Between 2030 and 2033, begin high-speed passenger service between Merced, Fresno and Bakersfield this is our highest priority.
 - By 2030, advance Northern and Southern California sections to 30% design so that construction can continue to progress when funding is available.



RAISE GRANT SCOPE AND SCHEDULE


- \$20 Million Federal RAISE grant for Early Site Activation
 - Historic Fresno Station renovation
 - New Depot Plaza
 - Chinatown Mobility Hub
- Design is underway, construction is scheduled to begin in 2026

Category	Category	2024		2025		2026		2027			2028			2029			2030			
Early Site Activation	Design																			
	Construction																			
HSR Station	Design																			
	Construction																			




PROJECT TEAM AND CHRONOLOGY

PROJECT TEAM ORGANIZATION CHART



PROJECT CHRONOLOGY





HISTORIC STATUS

National Register of Historic Places: Passenger Depot, Freight Depot Fresno Register of Historical Resources: Passenger Depot, Freight Depot and Pullman Shed

Period of Significance (Page & Turnbull recommendation): 1889-1932

Rehabilitation to comply with Secretary of the Interior's Standards


Environmental Review:

CEQA and NEPA Section 106 (SHPO)

PRC §5024 and §5024.5 (SHPO)




FRESNO HISTORIC TRAIN STATION





FRESNO HISTORIC TRAIN STATION



CHARACTER DEFINING FEATURES















1909 SITE PANORAMA






SIGNIFICANCE DIAGRAMS


SIGNIFICANT

CONTRIBUTING

NON-CONTRIBUTING

Non-contributing elements were largely built in the 1980s and generally are interior partitions







INVESTIGATIVE WORK


Pre-Design Work beginning 2022:

- LIDAR 3D scan by Locus Laser Scanning for Existing Building Condition Drawings in Revit
- Topographic Survey prepared by Aliquot Associates
- Site and Building Accessibility Surveys prepared by Robina Wright Architect & Associates
- Hazardous Materials Survey by Terracon Consultants
- Structural Materials Testing & Investigation by BSK Associates
- Materials Testing Report by Applied Materials & Engineering
- Geotechnical Design Criteria Memorandum by Rutherford + Chekene
- Structural Code Analysis and Conceptual Seismic Retrofit by Rutherford + Chekene
- Fire and Life Safety Report by Holmes
- Wood Member Identification by Flynn & Associates
- Archaeological Records Search Results Memorandum by Page & Turnbull
- Historic Character-Defining Features Memorandum and Diagrams by Page & Turnbull



EXISTING SITE PLAN










EXISTING PLAN







BASIS OF DESIGN

Basis of Design Retrofit Scope:


- Seismic Retrofit
- Accessibility Upgrades to exterior walks and interior path of travel
- Exterior Envelope Repairs for weather-resistance
- Architectural Repairs at locations of seismic work
- Life-safety and fire protection upgrades as required
- Warm Shell Condition


Schedule milestones:

- 4/2024: Approve Basis of Design
- 3/2025 or earlier: Complete CD documents
- 12/2025 or earlier: Approvals and Bid
- 1/2026 or earlier: Start Construction




PROPOSED PLAN








ACCESSIBILITY PLAN







PROPOSED ELEVATIONS

GENERAL NOTES

- NEW ASPHALT SHINGLE ROOFING SYSTEM AT SLOPED ROOF - OVER NEW 1/2" STRUCTURAL PLYWOOD SHEATHING OVER EXISTING SHEATHING.
- NEW SINGLE PLY COMPOSITE ROOFING SYSTEM AT FLAT ROOF - OVER NEW 1/2" STRUCTURAL PLYWOOD SHEATHING OVER EXISTING REPAIRED SHEATHING.
- SALVAGE AND REINSTALL CLAY TILE AND SUPPLEMENT AS NEEDED DURING REROOFING.
- ALL WOOD AND PLASTER NEED TO BE REPAINTED.
- 5. COLUMNS AT REAR WALKWAY EXHIBIT DELAMINATION OF WOOD AND PAINT, SPLITTING BETWEEN THE SHAFT AND CAPITAL, MINOR CRACKING AND CHARRING MARKS. PATCH AND REPAIR AS NEEDED.
- 'NO ACCESS' INDICATES AREAS NOT ACCESSIBLE FOR SURVEYING.

KEYNOTES

WOOD

- 1A. SHEATHING REPLACEMENT
- 1B. SHEATHING REPAIR
- 1C. WOOD REPAIR

GUTTER

2A. REPAIR/REPLACE GUTTER

PLASTER

3A. PATCH REPAIR

3B. PREP FOR PATCH AND REPAINT


3C. PATCH REPAIR AT OVERHANG UNDERSIDE

WINDOWS

4A. BOARD REMOVAL, REPLACE IF BROKEN

- 4B. PAINT REMOVAL
- 4C. REPAIR MULLIONS
- 4D. WINDOW IN POOR CONDITION, REPLACE/ REPAIR





SOUTH ELEVATION

