


PLANT LEGEND



STREET TREES FROM CITY OF FRESNO STREET







SMALL ON-SITE TREE (12'-15' DIAMETER) SUCH AS: CRAPE MYRTLE CV., PURPLE LEAF PLUM, ARBUTUS 'MARINA', REDBUD, PHOENIX MESQUITE, ITALIAN CYPRESS - 15 GAL

SHRUBS AND GROUND COVERS

MIXED SHRUBS WITH MUCOLS "LOW" WATER USE





MEDITERRANEAN AND NATIVE SHRUBS, WUCOLS 'MEDIUM' AND MIXED ZONES OF 'MEDIUM' AND 'LOW' WATER USE PLANTS SUCH AS: HESPERALOE SP RHAPHIOLEPIS SP DIETES IRRIOIDES NANDINA SP SALVIA SP.

AND ACCENT SHRUBS SUCH AS: LAVENDAR SP. ICEBERG ROSES FLOWER CARPET ROSES NANDINA SP. HEMEROCALLIS SP. ORNAMENTAL GRASSES

AND GROUND COVERS SUCH AS: PROSTRATE TEUCRIUM TRAILING ROSEMARY TRACHELOSPERMUM SP. GROUND COVER JUNIPERS

+ + + RECREATION TURF - BERMUDA FROM SOD

<u>NOTES</u>

CITY OF FRESNO NOTES:

TREES SHALL BE MAINTAINED IN GOOD HEALTH. HOWEVER, TREES MAY NOT BE TRIMMED OR PRUNED TO REDUCE THE NATURAL HEIGHT OR OVERALL CROWN OF THE TREE, EXCEPT AS NECESSARY FOR THE TREE AND PUBLIC SAFETY; OR AS MAY OTHERWISE BE APPROVED BY THE DEVELOPMENT DEPARTMENT.

LANDSCAPING MUST BE IN PLACE BEFORE ISSUANCE OF THE CERTIFICATE OF OCCUPANCY, A HOLD ON OCCUPANCY SHALL BE PLACED ON THE PROPOSED DEVELOPMENT UNTIL SUCH TIME THAT LANDSCAPING HAS BEEN APPROVED AND VERIFIED FOR PROPER INSTALLATION BY THE PLANNING DIVISION.

PRIOR TO FINAL INSPECTION, A WRITTEN CERTIFICATION, SIGNED BY A LANDSCAPE PROFESSIONAL APPROVED BY THE DIRECTOR, SHALL BE SUBMITTED STATING THAT THE REQUIRED LANDSCAPING AND IRRIGATION SYSTEM WAS INSTALLED IN ACCORDANCE WITH THE LANDSCAPING AND IRRIGATION PLANS APPROVED BY THE DEVELOPMENT SERVICES DIVISION, DEVELOPMENT DEPT.

NO STRUCTURES OF ANY KIND MAYBE INSTALLED OR MAINTAINED WITHIN THE LANDSCAPED AREAS. NO EXPOSED UTILITY BOXES, TRANSFORMERS, METERS, PIPING, (EXCEPTING THE BACKFLOW PREVENTION DEVICE) ETC., ARE ALLOWED TO BE LOCATED IN THE LANDSCAPE AREAS OR SETBACKS OR ON THE STREET FRONTAGES OF THE BUILDINGS. ALL TRANSFORMERS SHALL BE SHOWN ON THE PLAN. THE BACKFLOW DEVICE SHALL BE SCREENED BY LANDSCAPING OR SUCH OTHER MEANS AS MAY BE APPROVED.

ADDITIONAL NOTES: FINAL LOCATIONS OF TREES AND FINAL TREE COUNT TO BE ADJUSTED AFTER FINAL DESIGN OF UNDERGROUND UTILITIES, SITE AND STREET LIGHTING, TRANFORMER LOCATIONS, ETC.

PROJECT PLANS WILL COMPLY WITH THE REQUIREMENTS OF THE WATER EFFICIENT LANDSCAPE ORDINANCE (CCR § 490-495) JULY 9, 2015, APPLICABLE CITY OF FRESNO MUNICIPAL CODE SECTIONS INCLUDING ARTICLE 24 OF THE DEVELOPMENT CODE.

CALCULATIONS

PARKING LOT SHADE CALCULATION:

TOTAL SF OF PARKING AND DRIVEWAYS: 32,314 SF LESS AREA UNDER CARPORTS (8,820 SF) AREA TO BE SHADED 23,494 SF

SHADE FROM TREES ADJACENT TO PARKING AREAS/DRIVEWAYS: (PERIMETER TREES COUNTED AT 100%. TREES BETWEEN CARPORTS COUNTED, TREES BEHIND CARPORTS NOT COUNTED)

LARGE (962 SF): 9 = 8,658 SF 6 = 4,242 SFMEDIUM (707 SF): 16 = <u>5,024 SF</u> SMALL (314 SF): TOTAL SHADE FROM TREES 17,924 SF

PERCENT SHADE: PROJECT MEETS THE SHADE REQUIREMENT

TOTAL ONSITE TREE COUNT:

TOTAL NUMBER OF UNITS ON SITE: 64 UNITS TOTAL NUMBER OF REQUIRED PARKING SPACES ON SITE: 96 SPACES REQUIRED TREES AT I/UNIT + I/2 SPACES II2 TREES TOTAL NUMBER OF MEDIUM AND LARGE TREES, ONSITE: TOTAL NUMBER OF MEDIUM TREE EQUIVALENTS, ONSITE: TOTAL TREES

76.29%

PROJECT IS IN COMPLIANCE WITH TREE REQUIREMENT

STREET TREES

TOTAL LF FRONTAGE, BULLARD AVE 230 LF NUMBER OF STREET TREES AVERAGE SPACING 57.5' TOTAL LF FRONTAGE, DANTE AVE 649 LF NUMBER OF STREET TREES 50.0' AVERAGE SPACING

LANDSCAPE QUANTITIES

TOTAL ON-SITE LANDSCAPE AREA 68,766 SF ON-SITE TURF FOR RECREATION 4,828 SF (7.0%)

ON-SITE NON-TURF LANDSCAPE AREA 63,887 SF OFFSITE FRONTAGE

SHRUBS AND GROUND COVERS: 4,453 SF

MICRO IRRIGATION OF ALL SHRUBS AND TREES

ADDITIONAL STRATEGIES FOR WATER CONSERVATION ANTICIPATED:

 RAIN GAUGE FOR AUTOMATIC SHUT OFF OF IRRIGATION SYSTEM DURING PERIODS OF RAIN

SOIL MOISTURE SENSOR TO ACTIVATE/DEACTIVATE IRRIGATION VALVES

PRELIMINARY MWELO CALCULATION:

ETWU = 893,940 GAL/YRMAWA = 1,344,681 GAL/YR (at 55% allowance)

PRELIMINARY CALCULATION MEETS THE REQUIREMENTS OF MWELO

7790 N PALM AVE · FRESNO, CALIFORNIA 93711 T559.448.8400 · F559.448.8467 · www.sim-pbk.com THE ORCHARDS APARTMENTS - PHASE 2

PHASE 2 IS LOCATED ON NEC OF DANTE AVE & BULLARD AVE XXXX W. BULLARD AVE, FRESNO CA, 93722

CONCEPTUAL LANDSCPE PLAN

JOHN SMITH 18-52.I 04.29.19

Io. DATE DESCRIPTION
04.29.19 PLANNING SUBMITTAL

SCALE:1" = 30'-0" Sierra Designs, Inc 113 N. Church Street, Suite 310 Visalia, California 93291 Tele: 559.733.3690 SDI Project No. 19-014 4.25.2019