

ATTACHMENT B

CLARIFICATIONS AND EXCLUSIONS

CLARIFICATIONS

The following clarifications are hereby incorporated into the Contract by reference:

1. General:

- a. The General Contractor shall have the right to photograph the project, including the exterior elevation for use in General Contractor's promotional materials.
- b. The General Contractor shall not be held liable for any subcontractor, vendor or supplier directly contracted by the City or Tenant(s). Additionally, the General Contractor will be reimbursed for any costs or delays related to the aforementioned subcontractor, vendor or supplier failure. Quiring will provide scheduling and coordination with the City's own subcontractors.
- a. The one-year warranty period for all work shall commence upon substantial completion. The warranty on all mechanical equipment starts upon the equipment being started and tested during the final inspections phase. This could be as early as several months prior to obtaining a Certificate of Occupancy.
- c. The General Contractor's security measures are limited to 6' high, temporary fencing and temporary site security lighting. Any additional security measures, including but not limited to security guards, video surveillance or monitoring, other barriers or access control are to be by City.
- d. Exhibit A, "MOC #1" issued by iT Architecture on 10/27/2020 is included
- e. Exhibit B, responses to pre-bid RFIs 0002, 0003, and 0006-0010 are included.

2. Site Work & Building Demolition:

- An allowance of \$167,500 for Rule 16 gas and electric work has been included subject to adjustment pending final design from PG&E.
- b. All soils are assumed to be clean, non-hazardous.
- c. The following Value Engineering reductions have been included in the landscaping scope. Not including these items will result in an increase of \$66,680:
 - i. Plans call for 13,000 s.f. of bark and several trees shrubs and trees adjacent to the trash enclosure. These would be eliminated.
 - ii. Plans call for 5yds of soil amendment per 1,000 s.f. This is amended to 3 yds per 1,000 s.f.
 - iii. Plans show crushed rock adjacent to a double gate on the rear of the project. This will be eliminated.
 - iv. Plans show 5 gallon Xylosma shrubs spaced 3' O.C. These will be spaced 4' O.C.
 - v. Plans show Ligustrum Hedges along Airways Blvd and the drive approaches. These will be eliminated.
 - vi. Plans show Lantana shrub spaced 2'-6" O.C. These will be spaced 4' O.C.



- vii. Plans show the Myoporum ground cover spaced 3' O.C. These will be spaced 4' O.C.
- viii. Plans show the Dianella shurbs spaced 1' O.C. These will be spaced 2' O.C.
- ix. Plans show 5 gallon Oleo shrubs under the future car ports. These will be 1 gallon.
- x. Plans show Pistache trees to be 24" box. These will be 15 gallon.
- xi. Plans shown Lagertsrum trees to be 24" box. These will be 15 gallon.
- xii. Plans show the irrigation main to be 2 ½". This will be 2".
- xiii. Plans show (2) irrigation bubbler per tree. This will be changed to (1) bubbler per tree.
- xiv. The drip irrigation system will be installed above ground, with staples, under the bark ground cover.
- xv. Plans show a a controller and valves are two-way with a decoder system. This will be a conventional, solid state system.
- d. Site Furnishings; Benches are quoted as Dumor 98-601, an equivalent product to that specified. Multi-loop bike rack quoted as Dumor 125-40, an equivalent product to that specified.

3. Concrete and Masonry:

a. CMU, concrete, and grading are per Exhibit C, "CMU and Concrete Revisions". This document takes precedence over any conflicts with pre-bid RFI 0006.

4. Thermal & Moisture Protection:

- a. Insulation work is limited to only that which is shown on the plans and T-24 Energy Calculations, and includes R-30 unfaced batts at the underside of the roof deck, R-19 unfaced batts at 6" exterior walls full height and at 6" interior walls to 6" above ceiling, R-11 unfaced batts at 8" interior walls to underside of roof deck, and R-13 unfaced batts at 4" interior walls to 6" above ceiling. Insulation is scrim-faced where exposed.
- b. Termite flashing was assumed at complete building perimeters. Termite flashing is not shown at all location per the project documents.
- c. A sheet metal coping is provided at Building E along gridline 0 in lieu of a TPO roof.

5. Doors & Windows:

- a. Overhead Doors; Overhead doors quoted as Overhead Door Company Series 625, insulated, heavy-duty rolling service doors.
- b. Door hardware is provided per Exhibit D, "Door Hardware".

6. Finishes:

- a. Lath & Plaster; All building paper/moisture barrier and lath is continuous behind trim. Cutting of building paper & lath is only included where structural separation occurs.
 Plaster to receive paint. Light sand finish coat is to provide texture only, not final color.
- b. A slim-foot cove base was quoted at sealed concrete floor locations due to the specified base not meeting code requirements.
- Exposed structural steel system in open ceilings is not painted. Exposed exterior steel painted is included.
- d. EPX-1 is provided as a continuous flooring system with 4" cove base. PT-4 will lap over EPX-1 cove base and continue full height of wall unless indicated otherwise. EPX-1 is provided as 1



application of General Polymers 3579 standard epoxy primer/binder and 1 top coat of General Polymers 3741 coating.

7. Specialties:

- a. Signage work is limited to only that which is required by code, an exterior building address number sign, room ID tags, and kennel ID tags. Exterior building signage (i.e. keynote 16 on sheet A-3.0) and decorative sheet metal cut outs (i.e. keynote 13 on sheet A-3.0) are not included. Decorative, wayfinding, and other signage types are excluded ee Exclusions)
- b. Standard kennel runs are by Shor-Line. Top enclosure panels are provided for the exterior only. Interior dividing panels are partial isolation. "Bite Guard Kennel Plex Saloon Doors" not included.
- c. Medical grade casework (by the manufacturer Midmark) is provided in Rooms E107, E108, E111, E112, and E113, in lieu of millwork.
- d. Bathroom partitions are floor-mounted, overhead-braced, and solid plastic.

8. Equipment:

- a. Walk-in cooler A150 has exterior dimensions of 9'x12' per SPCA input, rather than 10'x12' as shown on the project plans
- b. Medical Equipment provided is per Exhibit E, "Medical Equipment".
- c. Additional animal control housing/cages are provided per Exhibit F, "Misc. Containment".

9. Furnishings:

a. All interior furnishings, fixtures and equipment are excluded. (see Exclusions).

10. Mechanical/Plumbing/Fire Protection:

a. The fire sprinkler system design assumes adequate water pressure and flow is available at the building. No provision has been made for a pump.

11. Low Voltage:

- a. Low voltage scope responsibilities are provided per Exhibit G, "Low Voltage Responsibilities". All work labeled as EC, IE, or OT is included.
- b. Work described or altered on the documents Exhibit H, "Camera Wiring Locations", and Exhibit I, "ISD Electrical Comments", is included.



EXCLUSIONS

The following exclusions are hereby incorporated into the Contract by reference:

- 1. Excludes all changes resulting from plan check, back check or other changes to the plans listed in Attachment "C". Furthermore, no allowance has been included in this contract price for any such changes.
- 2. Permits, assessments, utility connection costs and other such fees imposed by a third party with the authority over the project or site.
- 3. Excludes any other construction work outside the limits of construction as defined in the contract documents.
- 4. Design Fees.
- 5. Testing, Inspections, Special Inspections to be done by owner. Quiring, its subcontractors, and its design consultants to assist in the coordination as needed.
- 6. All Commissioning. Quiring, and its subcontractors, will assist and coordinate with commissioning requirements when provided.
- 7. Any work not specifically identified in the drawings or clarifications contained in this Attachment.



EXHIBIT A

MOC #1



MOC #1



Project: City of Fresno Animal Shelter

iT Job #: 19-061

Project Address: 5277 E. Airways Blvd.

Fresno, CA 93727

Plan Check No.: B20-11443 Local Jurisdiction: City of Fresno

Approval Date: TBD Date: 10/27/2020

This is a clarification and/or modification of a part of the project Contract Documents as a result of Contractor Bid Phase. Changes described herein shall be incorporated into the final Bid Documents

- 1-1 Revise Restroom Wall finish to be Fiberglass Reinforced Panels to +4'-0" off Finish Floor. Grout to floor with DILEX-AHKA Cove trim.
- 1-2 Revise Restroom Floors to be Honed concrete with clear polyurea concrete coating.
- 1-3 Rubber top-set base shall be used throughout wherever base is specified with the exception of restrooms.
- 1-4 Remove two non-ADA showers, one ADA shower to remain.
- 1-5 Remove soffit panels in the Sally Port, provide vinyl covered scrim sheet over insulation.
- 1-6 All storefronts to be Kawneer 450/451 or equal.
- 1-7 Building B roll up doors; change to pair of 3'x7' hollow metal doors with fixed leaf

1465 North Van Ness Avenue Fresno, California 9328



EXHIBIT B

PRE BID RFIS



5277 East Airways Boulevard, Fresno, California

From: Ross Goedde (Quiring General LLC)
To: Ross Goedde (Quiring General LLC)
Sent: Oct 8, 2020 at 10:12 PM UTC

RFI 0002 - Building A - Built-in Tall Cabinet Elevations

Status: Distributed

Due Date: Oct 8, 2020

Question

Ross Goedde (Quiring General LLC) on Oct 1, 2020 at 9:01 PM UTC

Building E, Keynote 16 calls out "Built-in tall cabinets" in Hall E117, but there is no elevation given for that location.

Keynote 16 is also called out in Surgery E111, for which elevation 6/A-8.3 is provided.

Please confirm that elevation 6/A-8.3 applies as a similar elevation for Hall E117.

O A-1.4 (See page 2)

Answer

todd@itarchinc.com on Oct 8, 2020 at 4:46 PM UTC


Yes, please provide base on elevation shown, all tall cabinets shall be typical.

Todd Clark | Vice President iT Architecture, Inc. 1465 N. Van Ness Ave. | Fresno, CA 93728 Office: (559) 442-4642 www.itarchinc.com>

Prepared by Ross Goedde

1







Answered and sent to manager

todd@itarchinc.com on Oct 8, 2020 at 4:46 PM UTC

· Answer added:

Yes, please provide base on elevation shown, all tall cabinets shall be typical.

Todd Clark | Vice President iT Architecture, Inc. 1465 N. Van Ness Ave. | Fresno, CA 93728 Office: (559) 442-4642 www.itarchinc.com>

Information edited

Ross Goedde (Quiring General LLC) on Oct 2, 2020 at 8:50 PM UTC

- · Reviewer added:todd@itarchinc.com
- · Reviewer removed:Ross Goedde (Quiring General LLC)

Question drafted and sent to reviewer

Ross Goedde (Quiring General LLC) on Oct 1, 2020 at 9:02 PM UTC

· Question added:

Building E, Keynote 16 calls out "Built-in tall cabinets" in Hall E117, but there is no elevation given for that location.

 $\label{tensor} \mbox{Keynote 16 is also called out in Surgery E111, for which elevation 6/A-8.3 is provided.}$

Please confirm that elevation 6/A-8.3 applies as a similar elevation for Hall E117.

- · Title added:Building A Built-in Tall Cabinet Elevations
- · Submitter added:Ross Goedde (Quiring General LLC)
- Manager added:Ross Goedde (Quiring General LLC)
- · References added:

[O] A-1.4

- · Number added:0002
- · Reviewer added:Ross Goedde (Quiring General LLC)
- Due date added:Oct 8, 2020

Prepared by Ross Goedde

3



5277 East Airways Boulevard, Fresno, California

From: Ross Goedde (Quiring General LLC) To: Ross Goedde (Quiring General LLC) Sent: Oct 8, 2020 at 10:12 PM UTC

RFI 0003 - Building E - Interior Storefront **Windows Missing**

Status: Distributed

Due Date: Oct 9, 2020

Question

Ross Goedde (Quiring General LLC) on Oct 1, 2020 at 9:04 PM UTC

Elevations 1 & 8 on A-8.3 show two interior storefront windows between Lab E107 and Treatment E112.

A-1.4 shows the upper cabinets spaced to accommodate such windows, but the windows themselves are not shown.

Please confirm that the windows are to be installed per elevations 1 & 8 on A-8.3.

- O A-8.3 (See page 2)
- O A-8.3 (See page 3)
- O A-1.4 (See page 4)

Answer

todd@itarchinc.com on Oct 8, 2020 at 4:47 PM UTC

Please see attached floor plan.

Todd Clark | Vice President iT Architecture, Inc. 1465 N. Van Ness Ave. | Fresno, CA 93728 Office: (559) 442-4642 www.itarchinc.com<http://www.itarchinc.com>




SKMBT_C22020100809400.pdf (See page 5)


Prepared by Ross Goedde

1





















Answered and sent to manager

todd@itarchinc.com on Oct 8, 2020 at 4:47 PM UTC

· Answer added:

Please see attached floor plan.

Todd Clark | Vice President iT Architecture, Inc. 1465 N. Van Ness Ave. | Fresno, CA 93728 Office: (559) 442-4642 www.itarchinc.com<http://www.itarchinc.com>

· References added:



SKMBT_C22020100809400.pdf

Question sent to reviewer

Ross Goedde (Quiring General LLC) on Oct 2, 2020 at 8:50 PM UTC

- · Number added:0003
- · Due date added:Oct 9, 2020

Information edited

Ross Goedde (Quiring General LLC) on Oct 2, 2020 at 8:50 PM UTC

· Reviewer added:todd@itarchinc.com

Question edited

Ross Goedde (Quiring General LLC) on Oct 1, 2020 at 9:06 PM UTC

- · References added:
 - [O] A-8.3
- [O] A-8.3
- (c) A-1.4

Question drafted by manager

Ross Goedde (Quiring General LLC) on Oct 1, 2020 at 9:04 PM UTC

· Question added:

Elevations 1 & 8 on A-8.3 show two interior storefront windows between Lab E107 and Treatment E112.

A-1.4 shows the upper cabinets spaced to accommodate such windows, but the windows themselves are not shown.

Please confirm that the windows are to be installed per elevations 1 & 8 on A-8.3.

- . Title added:Building E Interior Storefront Windows Missing
- · Submitter added: Ross Goedde (Quiring General LLC)
- · Manager added:Ross Goedde (Quiring General LLC)

Prepared by Ross Goedde



5277 East Airways Boulevard, Fresno, California

RFI 0006 - Miscellaneous CMU Questions

Status: Answered

Due Date: Oct 23, 2020

Question

Ross Goedde (Quiring General LLC) on Oct 12, 2020 at 4:39 PM PDT

There are several questions in this RFI.

There are some spots in the drawings that show a 4" curb under masonry walls at kennels, while other seem to call for the masonry to sit directly on the slab. Sections for this condition callout detail 12/S501, but this detail does not exist.

Detail 4/A1.2 shows the kennel dividing walls to be 4'-6", while wall type M2 call for the wall to be 6'-0".

There is no connection detail between the building exterior CMU walls, and the kennel dividing CMU walls.

Please confirm/provide the following.

- 1. Confirm the CMU walls are to sit directly on the slab (no 4" curb).
- 2. Please provide detail 12/S501
- 3. Confirm the height of CMU kennel dividing walls (wall type M2).
- 4. Provide a connection detail between the building exterior CMU walls and the kennel dividing CMU walls.
- [O] S403 (See page 2)
- O A-1.2 (See page 3)
- O A-1.2 (See page 4)

Answer

todd@itarchine.com on Oct 16, 2020 at 7:55 AM PDT

For your records.

Todd Clark | Vice President iT Architecture, Inc. 1465 N. Van Ness Ave. | Fresno, CA 93728 Office: (559) 442-4642 www.itarchinc.com<http://www.itarchinc.com>




19-061-RFI-006.pdf (See page 5)


Prepared by Ross Goedde

1
















5277 East Airways Boulevard, Fresno, California

From: Ross Goedde (Quiring General LLC)

To: todd@itarchinc.com

Sent: Oct 12, 2020 at 4:39 PM PDT

RFI 0006 - Miscellaneous CMU Questions

Status: Sent to reviewer

Due Date: Oct 23, 2020

Question

Ross Gnedde (Quiring General LLC) on Oct 12, 2020 at 4:39 PM PDT

There are several questions in this RFI.

There are some spots in the drawings that show a 4" curb under masonry walls at kennels, while other seem to call for the masonry to sit directly on the slab. Sections for this condition callout detail 12/S501, but this detail does not exist.

Detail 4/A1.2 shows the kennel dividing walls to be 4'-6", while wall type M2 call for the wall to be 6'-0". A '-6" Is copped to the Kenter walls of the connection detail between the building exterior CMU walls, and the kennel dividing CMU walls.

WE WILL PROPE DENALL Please confirm/provide the following.

- Please confirm/provide the following.

 1. Confirm the CMU walls are to sit directly on the slab (no 4" curb). All Kenther walls should be the Provide detail 12/5501 To Follow 3. Confirm the height of CMU kennel dividing walls (wall type M2). 4 6" CMU w 1 1 6" Kenther of Top 4. Provide a connection detail between the building exterior CMU walls and the kennel dividing CMU walls. To Follow


- (O) S403 (See page 2)
- O A-1.2 (See page 3)
- (See page 4)

ASSUME ALL KENNEL WALLS SIT DIRECTLY ON THE SLAB. THE 4" CONCRETE CURB SHOWN IN 4/A-1.2 ONLY APPLIES AT THE PASS THROUGH FOR THE ANIMALS TO MOVE FROM INTERIOR TO EXTERIOR.


Prepared by Ross Goedde

1

















	-1.2		Ross Goedde (Quiring General LLC) on Oct 12, 2020 at 4.39 PM PDT
-	Wall Schedule	(Pana)	
	Mark Description		
	1 DE ET LASTE S'OTHERN A CONCRETE CARRY THE OF THE ALL ST INDEPENDENCE OF REDOT MANY ADDRESS OF A SERVICE AND SECULAR ASSESSMENT AND ADDRESS OF REDOT MANY ADDRESS OF A SERVICE SECULAR SECULAR ASSESSMENT AND ADDRESS OF A SERVICE ADDRESS OF A SERVICE ADDRESS OF A SERVICE AND ADDRESS OF A SERVICE A		
	2 8' N 23' SA YETAL STUDS & THOM DIAD TO DOCK ADDIE TROYDE DELIVERED OF 5' S' THE VISITANI GRAD FILL HOLD BOTH SODD OF FRANKS PROVIDE SHE SATT NOWATON THE FEBRUAR FRANKS SATELY.		
	2 8' 1. 20 SAMETAL STIDS & WINDE FROM SUAD TO A FORT IT FOOMS MOREST ADMICENT SUITED THAN THAN THAT IT WINDERS TO BE THE N. SIMBLY DOWN TALL HOOM DOT'S 2015 OF FRANCIS FROM THAN FOOMS AND STIDE STIDES.		
	# 3 B C N 30 GA MÉTAL SÉLOS & YE GIC FROM SUAD FOLK TON' ELABORE HOMEST ADUALOUS COLLAND FILANCE MODERS (1) LAMBER OF 1885 1975 IN SEMPLAN BOARD FILL HOMES GOTH 6055- OF MANNES FROM FORETHE FROM BOARD A		
	AND CONSETT MADERAL AT PRESSOR THAT AND BUSINESS APPLY ADMINISTRATION OF THE PROPERTY AND T		
	MISTON CONTRETE MADDRET AND PRESSON FACE AT 8 SOCIENTED EDITING CONTROL PROMISED TO CONTROL PROMISED AND A FALL LOCATION OF REFER TO EXTENDED AND SECTION.		
	W3 BASING CONCRETE MASCHART AND PRESSOR FACE INSOLUTION SAND TO SHE AFF PROVIDE 3 SOFT THE ISSUED OF THE PROVIDE OF THE PROVID		
	51 GEM MSDED NUMBER BY LENDE CHOSE GOOD STORERED THANCER THEFAST AND GEM THE FAST THAN CONTRACTOR THAN CONTRAC		
50.	52 GER ANDRED RUMMY MILL FASH CONTON LONGED STORETHING (MARKED THEFAD) 3. 450 SERIES 2" N. 4 1/2" AFT SHOULD PINE SUICING.		
	ALL NEEDS ANLE TO RECEIVE 4-19 BATT MOUNTONINGS OF CRANCE NOTED FOR THE CALL TRANNING DETAILS REFER TO SHEET ASSESSMENT OF THE METER TO SHEET ASSESSMENT OF THE PROPERTY OF TH		
	ALL PARTITIONS NOT OTHORASE NOTED ON PLANS SHILL BE TYPE W		
	(3)		







Question drafted and sent to reviewer

Ross Goedde (Quiring General LLC) on Oct 12, 2020 at 4.39 PM PDT

· Question added:

There are several questions in this RFI.

There are some spots in the drawings that show a 4" curb under masonry walls at kennels, while other seem to call for the masonry to sit directly on the slab. Sections for this condition callout detail 12/S501, but this detail does not exist.

Detail 4/A1.2 shows the kennel dividing walls to be 4'-6", while wall type M2 call for the wall to be 6'-0".

There is no connection detail between the building exterior CMU walls, and the kennel dividing CMU walls.

Please confirm/provide the following.

- Confirm the CMU walls are to sit directly on the slab (no 4" curb).
 Please provide detail 12/S501

- Confirm the height of CMU kennel dividing walls (wall type M2).
 Provide a connection detail between the building exterior CMU walls and the kennel dividing CMU walls.
- · Title added: Miscellaneous CMU Questions
- · Submitter added:Ross Goedde (Quiring General LLC)
- Manager added:Ross Goedde (Quiring General LLC)
- · References added:
 - [0] 5403
- [O] A-1.2
- (O) A-1.2
- · Number added:0006
- · Reviewer added:todd@itarchinc.com
- · Due date added:Oct 23, 2020

Prepared by Ross Goedde

5



Answered and sent to manager

todd@itarchinc.com on Oct 16, 2020 at 7:55 AM PDT

· Answer added:

For your records.

Todd Clark | Vice President iT Architecture, Inc. 1465 N. Van Ness Ave. | Fresno, CA 93728 Office: (559) 442-4642 www.itarchinc.com<http://www.itarchinc.com>

· References added:



19-061-RFI-006.pdf

Question drafted and sent to reviewer

Ross Goedde (Quiring General LLC) on Oct 12, 2020 at 4:39 PM PDT

· Question added:

There are several questions in this RFI.

There are some spots in the drawings that show a 4" curb under masonry walls at kennels, while other seem to call for the masonry to sit directly on the slab. Sections for this condition callout detail 12/S501, but this detail does not exist.

Detail 4/A1.2 shows the kennel dividing walls to be 4'-6", while wall type M2 call for the wall to be 6'-0".

There is no connection detail between the building exterior CMU walls, and the kennel dividing CMU walls,

Please confirm/provide the following.

- 1. Confirm the CMU walls are to sit directly on the slab (no 4" curb).
- 2. Please provide detail 12/S501
- 3. Confirm the height of CMU kennel dividing walls (wall type M2).
- 4. Provide a connection detail between the building exterior CMU walls and the kennel dividing CMU walls.
- · Title added:Miscellaneous CMU Questions
- . Submitter added:Ross Goedde (Quiring General LLC)
- · Manager added:Ross Goedde (Quiring General LLC)
- · References added:



[O] A-1.2



- Number added:0006
- · Reviewer added:todd@itarchinc.com
- · Due date added:Oct 23, 2020

Prepared by Ross Goedde

10



5277 East Airways Boulevard, Fresno, California

From: Ross Goedde (Quiring General LLC)
To: Ross Goedde (Quiring General LLC)
Sent: Oct 14, 2020 at 6:15 PM UTC

RFI 0007 - Site Concrete Keynotes

Status: Distributed

Due Date: Oct 23, 2020

Question

Ross Goedde (Quiring General LLC) on Oct 13, 2020 at 10:13 PM UTC

There are two questions in this RFI.

On the W side of Bldg A, the handicap concrete stalls do not have a callout. On the N side of Bldg B, the handicap stall is called out as G38. Please confirm that the handicap stalls along Bldg A should be G38.

The site concrete between the various buildings is typically called out as G6 or G43. Please confirm the delineation between these two different concrete sections. Please confirm that, generally, G6 is to be installed under the building roof line, while G43 is to be installed in uncovered areas.

- C1.2 (See page 2)
- O C1.3 (See page 3)
- © C1.3 (See page 4)
- O C1.2 (See page 4)

Prepared by Ross Goedde

1




Answer

hal@lore-engineering.com on Oct 14, 2020 at 6:06 PM UTC

Ross, see below response to the RFI.

- 1. The handicap concrete stalls along building A are G38 keynote type concrete.
- The keynote G6 is sidewalk concrete and applies under the building roof line while keynote G43 concrete light duty vehicular rated concrete and is delineated by a hatch between buildings.


Hal Lore, PE Lore Engineering, Inc 559-297-5200, Ext: 1#




Prepared by Ross Goedde

5
















Distributed

Ross Goedde (Quiring General LLC) on Oct 14, 2020 at 6:15 PM UTC

· Sent to:Ross Goedde (Quiring General LLC)

Answered and sent to manager

hal@lore-engineering.com on Oct 14, 2020 at 6:06 PM UTC

· Answer added:

Ross, see below response to the RFI.

- The handicap concrete stalls along building A are G38 keynote type concrete.
- The keynote G6 is sidewalk concrete and applies under the building roof line while keynote G43 concrete light duty vehicular rated concrete and is delineated by a hatch between buildings.

Hal Lore, PE Lore Engineering, Inc 559-297-5200, Ext: 1#

Question drafted and sent to reviewer

Ross Goedde (Quiring General LLC) on Oct 13, 2020 at 10:13 PM UTC

· Question added:

There are two questions in this RFI.

On the W side of Bldg A, the handicap concrete stalls do not have a callout. On the N side of Bldg B, the handicap stall is called out as G38. Please confirm that the handicap stalls along Bldg A should be G38.

The site concrete between the various buildings is typically called out as G6 or G43. Please confirm the delineation between these two different concrete sections. Please confirm that, generally, G6 is to be installed under the building roof line, while G43 is to be installed in uncovered areas.

- · Title added:Site Concrete Keynotes
- Submitter added:Ross Goedde (Quiring General LLC)
- · Manager added:Ross Goedde (Quiring General LLC)
- · References added:

[O] C1.2

[O] C1.3

[O] C1.3

[O] C1.2

- · Number added:0007
- Reviewer added:hal@lore-engineering.com
- · Due date added:Oct 23, 2020

Prepared by Ross Goedde

6



5277 East Airways Boulevard, Fresno, California

RFI 0008 - Miscellaneous Casework Questions

Status: Answered

Due Date: Oct 23, 2020

Question

Ross Goedde (Quiring General LLC) on Oct 13, 2020 at 3:28 PM PDT

There are three questions in this RFI.

Elevations for rooms A103 and A130 are not shown on the A-8.X sheets. Please provide elevations for this casework.

For the lockers in A116, please confirm that these should have an integral lock with a number identification for each. Please provide specifications for any specialty hardware.

Please provide the finish for the bench in room A116.

O A-7.0 (See page 2)

[O] A-1.1 (See page 3)

Answer

todd@itarchinc.com on Oct 16, 2020 at 7:45 AM PDT

For your records.

Todd Clark | Vice President iT Architecture, Inc. 1465 N. Van Ness Ave. | Fresno, CA 93728 Office: (559) 442-4642 www.itarchinc.com<http://www.itarchinc.com>




19-061-RFI-008.pdf (See page 4)


Prepared by Ross Goedde

1











5277 East Airways Boulevard, Fresno, California

From: Ross Goedde (Quiring General LLC)

To: todd@itarchinc.com
Sent: Oct 13, 2020 at 3:29 PM PDT

RFI 0008 - Miscellaneous Casework Questions

Status: Sent to reviewer

Due Date: Oct 23, 2020

Question

Ross Goedde (Quiring General LLC) on Oct 13, 2020 at 3:28 PM PDT

There are three questions in this RFI.

Elevations for rooms A103 and A130 are not shown on the A-8.X sheets. Please provide elevations for this casework.

A-10-3-1 A130 SHALL MATCOL A131 - 15/A-8.1 19/A-8.

For the lockers in A116, please confirm that these should have an integral lock with a number identification for each. Please provide specifications for any specialty hardware. Not REC 10 - Provide Loop HARDLEC FOL 17.

Please provide the finish for the bench in room A116. PT


(a) A-7.0 (See page 2)

[0] A-1.1 (See page 3)


Prepared by Ross Goedde

1











Question drafted and sent to reviewer

Ross Goedde (Quiring General LLC) on Oct 13, 2020 at 3:28 PM PDT

· Question added:

There are three questions in this RFI.

Elevations for rooms A103 and A130 are not shown on the A-8.X sheets. Please provide elevations for this casework.

For the lockers in A116, please confirm that these should have an integral lock with a number identification for each. Please provide specifications for any specialty hardware.

Please provide the finish for the bench in room A116.

- · Title added:Miscellaneous Casework Questions
- · Submitter added:Ross Goedde (Quiring General LLC)
- · Manager added:Ross Goedde (Quiring General LLC)
- · References added:

O A-7.0

(O) A-1.1

- · Number added:0008
- · Reviewer added:todd@itarchinc.com
- Due date added:Oct 23, 2020

Prepared by Ross Goedde

4



Answered and sent to manager

todd@itarchinc.com on Oct 16, 2020 at 7:45 AM PDT

· Answer added:

For your records.

Todd Clark | Vice President iT Architecture, Inc. 1465 N. Van Ness Ave. | Fresno, CA 93728 Office: (559) 442-4642 www.itarchinc.com<http://www.itarchinc.com>

· References added:



19-061-RFI-008.pdf

Question drafted and sent to reviewer

Ross Goedde (Quiring General LLC) on Oct 13, 2020 at 3:28 PM PDT

· Question added:

There are three questions in this RFI.

Elevations for rooms A103 and A130 are not shown on the A-8.X sheets. Please provide elevations for this casework.

For the lockers in A116, please confirm that these should have an integral lock with a number identification for each. Please provide specifications for any specialty hardware.

Please provide the finish for the bench in room A116.

- · Title added:Miscellaneous Casework Questions
- · Submitter added:Ross Goedde (Quiring General LLC)
- · Manager added:Ross Goedde (Quiring General LLC)
- · References added:





- · Number added:0008
- · Reviewer added:todd@itarchinc.com
- · Due date added:Oct 23, 2020

Prepared by Ross Goedde

8



5277 East Airways Boulevard, Fresno, California

RFI 0009 - Overhead Door Specifications

Status: Answered

Due Date: Oct 16, 2020

Question

Ross Goedde (Quiring General LLC) on Oct 13, 2020 at 3:31 PM PDT

Please confirm that the roll-up doors on the project should be insulated.

Please provide a finish for the roll-up doors (paint, powder coat, etc.).

Answer

todd@itarchinc.com on Oct 16, 2020 at 7:44 AM PDT

For your records.

Todd Clark | Vice President 1465 N. Van Ness Ave. | Fresno, CA 93728 Office: (559) 442-4642 www.itarchinc.comhttp://www.itarchinc.com



19-061-RFI-009.pdf (See page 2)

Prepared by Ross Goedde

1



5277 Exst Arways Boulevard, Fresno, California

From: Ross Goedde (Quiring General LLC)

To: todd@itarchinc.com

Sent: Oct 14, 2020 at 5:36 PM UTC

RFI 0009 - Overhead Door Specifications

Status: Sent to reviewer

Due Date: Oct 16, 2020

Question

Ross Goedde (Quiring General LLC) on Oct 13, 2020 at 10:31 PM UTC

Please confirm that the roll-up doors on the project should be insulated.

Please provide a finish for the roll-up doors (paint, powder coat, etc.).

OVERHEAD STEEL DOOR 625 - 62My

SEE ATTACHED BROCHURE.
EQUAL ALTERNATES ACCEPTABLE

Prepared by Ross Goedde

1



Answered and sent to manager

todd@itarchinc.com on Oct 16, 2020 at 7:45 AM PDT

· Answer added:

For your records.

Todd Clark | Vice President iT Architecture, Inc. 1465 N. Van Ness Ave. | Fresno, CA 93728 Office: (559) 442-4642 www.itarchinc.com<http://www.itarchinc.com>

· References added:



19-061-RFI-009.pdf

Question sent to reviewer

Ross Goedde (Quiring General LLC) on Oct 14, 2020 at 10:36 AM PDT

· Due date updated:Oct 16, 2020

Question returned to manager 5

Ross Goedde (Quiring General LLC) on Oct 14, 2020 at 10:36 AM PDT

. Message:Need to resend to Todd

Question drafted and sent to reviewer

Ross Goedde (Quiring General LLC) on Oct 13, 2020 at 3:31 PM PDT

· Question added:

Please confirm that the roll-up doors on the project should be insulated.

Please provide a finish for the roll-up doors (paint, powder coat, etc.).

- · Title added:Overhead Door Specifications
- Submitter added:Ross Goedde (Quiring General LLC)
- · Manager added:Ross Goedde (Quiring General LLC)
- Number added:0009
- · Reviewer added:todd@itarchinc.com
- Due date added:Oct 23, 2020

3 Created with PlanGrid Prepared by Ross Goedde











STORMTITE" MODEL 625

Style, function and thermal efficiency.

When overall performance and thermal efficiency are as essential in a rolling service door as are versatile good looks, the Stormtite™ 625 meets specification and exceeds all expectations. This heavy-duty door features insulated slats in a variety of materials - galvanized steel, stainless steel or aluminum - and offers optional wind load protection up to 170 psf. Designed to fit openings up to 30'4" wide and 28'4" high (9246 mm x 8636 mm) and offered with a broad range of product options, the versatility and functionality of the Stormtite" 625 ensures that your design requirements will be met with ease, functionality and style.



White finish. Installation and service: Overhead Door Company of Concord®

Slat data

F-265i slat

Slat	Opening width	Standard	Optional
F265i	Thru 30°4° (9246 mm)	24 ga.	22, 20, 18 ga. 22, 20 ga. ss .040° alum., 18 ga.

Slats are galvanized and painted, stainless steel (specify finish) or aluminum (specify finish). Gauges reflect front slat; back slat is 24-gauge on steel and stainless steel; 22-gauge on aluminum.



R-value* 7.7 (1.35 W/Msq) Smoke generation = 10 Flame spread = 5 STC = 21



The IECC listed air infiltration option meets code requirements for an air infiltration rating lower than than 1.0 cfm/ft2 for rolling steel doors.

This superior perimeter sealing system includes:

- · Guide cover and cap
- Dual brush guide seal
- Lintel seal
- Bottom astragal

Finish options

Finish details				
Standard polyester base coat	Two-coat system with polyester based top coat.			
PowderGuard® Premium powder coat	Weather resistant polyester powder coat available in approximately 200 colors; custom color match and EZ Clean treatment options available.			
PowderGuard® Zinc finish	Zinc enriched powder coat provides excellent corrosion protection that outperforms both hot dipped and cold galvanized steel. Color selection from approximately 200 powder coat colors; custom color match also available.			
PowderGuard® Textured finish	Industrial textured powder coat provides a thicker, more scratch resistant coat for added product protection.			



Actual colors may vary from brochure due to fluctuations in the printing process. Always request a color sample from your Overhead Door $^{\bowtie}$ Distributor for accurate color matching.

overheaddoor.com

3





The original, innovative choice for unequalled quality and service.

Overhead Door Corporation pioneered the upward-acting door industry, inventing the first upward-acting door in 1921 and the first electric door operator in 1926. Today, we continue to be the industry leader through the strength of our product innovation, superior craftsmanship and outstanding customer support, underscoring a legacy of quality, expertise and integrity. That's why design and construction professionals specify Overhead Door™ products more often than any other brand. Our family of over 400 Overhead Door™ Distributors across the U.S. and Canada not only share our name and logo, but also our commitment to excellence.





2501 S. State Hwy. 121 Bus., Suite 200, Lewisville, TX 75067 1-800-929-DOOR • sales@overheaddoor.com overheaddoor.com

©2018 Overhead Door Corporation. Overhead Door and Stormitte are trademarks and the Red Ribbon logo is a registered trademark of Overhead Door Corporation. All other trademarks are property of their rightful owners. Consistent with our policy of continuing product improvement, we reserve the right to change product specifications without notice or obligation. C900-073 10/18



5277 East Airways Boulevard, Fresno, California

RFI 0010 - Acoustical Ceiling Discrepancies

Status: Answered

Due Date: Oct 23, 2020

Question

Ross Goedde (Quiring General LLC) on Oct 13, 2020 at 3:58 PM PDT

Please clarify the follow discrepancies between the architectural RCPs and the interior design RCPs.

- 1. Room A102 Sheet A-2.0 notes this as C1. Sheet ID-5.0 notes this as ACT-2. Room A142 Sheet A-2.0 notes this as C1. Sheet ID-5.0 notes this as ACT-2. 3. Room A146 Sheet A-2.0 notes this as C3. Sheet ID-5.0 notes this as ACT-1. 4. Room A147 Sheet A-2.0 notes this as C3. Sheet ID-5.0 notes this as ACT-1.
- 5. Architectural drawings note C3 to be a 2'x2' tile, while equivalent callout ACT-2 on interior design drawings calls for a 2'x4' tile.

Answer

todd@itarchinc.com on Oct 16, 2020 at 7:44 AM PDT

For your records.

Todd Clark | Vice President iT Architecture, Inc. 1465 N. Van Ness Ave. | Fresno, CA 93728 Office: (559) 442-4642 www.itarchinc.com<http://www.itarchinc.com>



19-061-RFI-010.pdf (See page 2)

Prepared by Ross Goedde

1



5277 East Airways Boulevard, Fresno, California

From: Ross Goedde (Quiring General LLC)

To: todd@itarchinc.com

Sent: Oct 13, 2020 at 11:02 PM UTC

RFI 0010 - Acoustical Ceiling Discrepancies

Status: Sent to reviewer

Due Date: Oct 23, 2020

Question

Ross Goedde (Quiring General LLC) on Oct 13, 2020 at 10:58 PM UTC

Please clarify the follow discrepancies between the architectural RCPs and the interior design RCPs.

1. Room A102 - Sheet A-2.0 notes this as C1. Sheet ID-5.0 notes this as ACT-2.

2. Room A142 - Sheet A-2.0 notes this as C1. Sheet ID-5.0 notes this as ACT-2.

Room A146 - Sheet A-2.0 notes this as C3. Sheet ID-5.0 notes this as ACT-1.
 Room A147 - Sheet A-2.0 notes this as C3. Sheet ID-5.0 notes this as ACT-1.

5. Architectural drawings note C3 to be a 2'x2' tile, while equivalent callout ACT-2 on interior design drawings calls for a 2'x4' tile.

ALL CEILINUS SHALL POR PEK ARCHITECTUME DWG'S WE WILL UPDATE ID SHARES TO MARCH

Prepared by Ross Goedde

1



Question sent to reviewer

Ross Goedde (Quiring General LLC) on Oct 13, 2020 at 11:02 PM UTC

- · Reviewer added:todd@itarchinc.com
- · Due date added:Oct 23, 2020

Information edited

Ross Goedde (Quiring General LLC) on Oct 13, 2020 at 11:00 PM UTC

· Number added:0010

Question drafted by manager

Ross Goedde (Quiring General LLC) on Oct 13, 2020 at 10:58 PM UTC

· Question added:

Please clarify the follow discrepancies between the architectural RCPs and the interior design RCPs.

- Room A102 Sheet A-2.0 notes this as C1. Sheet ID-5.0 notes this as ACT-2.
 Room A142 Sheet A-2.0 notes this as C1. Sheet ID-5.0 notes this as ACT-2.
 Room A146 Sheet A-2.0 notes this as C3. Sheet ID-5.0 notes this as ACT-1.
 Room A147 Sheet A-2.0 notes this as C3. Sheet ID-5.0 notes this as ACT-1.

- 5. Architectural drawings note C3 to be a 2'x2' tile, while equivalent callout ACT-2 on interior design drawings calls for a 2'x4'
- · Title added:Acoustical Ceiling Discrepancies
- · Submitter added:Ross Goedde (Quiring General LLC)
- · Manager added:Ross Goedde (Quiring General LLC)

Prepared by Ross Goedde

2



Answered and sent to manager

todd@itarchinc.com on Oct 16, 2020 at 7:45 AM PDT

· Answer added:

For your records.

Todd Clark | Vice President iT Architecture, Inc. 1465 N. Van Ness Ave. | Fresno, CA 93728 Office: (559) 442-4642 www.itarchinc.com<http://www.itarchinc.com>

· References added:



19-061-RFI-010.pdf

Question sent to reviewer

Ross Goedde (Quiring General LLC) on Oct 13, 2020 at 4:02 PM PDT

- · Reviewer added:todd@itarchinc.com
- · Due date added:Oct 23, 2020

Information edited

Ross Goedde (Quiring General LLC) on Oct 13, 2020 at 4:00 PM PDT

· Number added:0010

Question drafted by manager

Ross Goedde (Quiring General LLC) on Oct 13, 2020 at 3:58 PM PDT

· Ouestion added:

Please clarify the follow discrepancies between the architectural RCPs and the interior design RCPs.

- 1. Room A102 Sheet A-2.0 notes this as C1. Sheet ID-5.0 notes this as ACT-2.
- 2. Room A142 Sheet A-2.0 notes this as C1. Sheet ID-5.0 notes this as ACT-2.
- 3. Room A146 Sheet A-2.0 notes this as C3. Sheet ID-5.0 notes this as ACT-1.
- 4. Room A147 Sheet A-2.0 notes this as C3. Sheet ID-5.0 notes this as ACT-1.
- 5. Architectural drawings note C3 to be a 2'x2' tile, while equivalent callout ACT-2 on interior design drawings calls for a 2'x4'
- · Title added: Acoustical Ceiling Discrepancies
- · Submitter added:Ross Goedde (Quiring General LLC)
- · Manager added:Ross Goedde (Quiring General LLC)

Prepared by Ross Goedde Created with PlanGrid



EXHIBIT C

CMU AND CONCRETE REVISIONS



Building CMU and Concrete Clarifications and Revisions to RFI 0006

10/23/2020

ALL SCOPE NOT DIRECTLY MENTIONED IN THIS DOCUMENT REMAINS THE SAME

Building Concrete

- All flatwork/slab within the RED highlighted zones
- CMU Footings (does not include trash enclosure or other site CMU walls)
- All CMU to receive a 4" (min.) curb poured integral to the slab
- Concrete curb to be level, 4" AFF accounting for floor sloping to trench drains.
- 3" of compacted, clean gravel, max. 3/4" with a vapor retarder barrier and 3" of clean damp sand under all flatwork/slab in this scope

Site Concrete


- All flatwork outside of the RED highlighted zones

CMU


- All CMU to sit on a concrete curb 4" AFF

Refer to notes in RED on the following pages and Detail 1 and Detail 2 at the end of this document.




































EXHIBIT D

DOOR HARDWARE



GROUP 01:

TOP/BOTTOM OFFSET PIVOT: PER MANUFACTURER

CONCEALED OVERHEAD CLOSER: PER MANUFACTURER

CONCEALED ROD EXIT DEVICE: Sim. Von Duprin 99L Series

ELECTRIC STRIKE: HES 9600 x US32D

CARD READER: by others
THRESHOLD: PEMKO

DOOR BOTTOM: PEMKO 315CN WEATHERSTRIP: PEMKO 303AS

GROUP 02:

PR. BUTTS: BB1279 4-1/2" X 4-1/2" X 626, HAGGER

EXIT DEVICE: VON DUPRIN 99LX996L
RIM CYLINDER: Schlage 20-057 x 626
ELECTRIC STRIKE: HES 9600 x US32D

CARD READER: by others
CLOSER: LCN 1450

WALL BUMPER: HAGER 236W 626
THRESHOLD: PEMKO 171A
DOOR BOTTOM: PEMKO 315CN
WEATHERSTRIP: PEMKO 303AS

GROUP 03:

PR. BUTTS: BB1279 4-1/2" X 4-1/2" X 626, HAGGER STOREROOM LOCKSET: SCHLAGE NEPTUNE, AL80PD X 626

ELECTRIC STRIKE: HES 8000 x 801 x US32D

CARD READER: by others
CLOSER: LCN 1450

WALL BUMPER: HAGER 236W 626

GROUP 04:

PR. BUTTS: BB1279 4-1/2" X 4-1/2" X 626, HAGGER STOREROOM LOCKSET: SCHLAGE NEPTUNE, AL80PD X 626

ELECTRIC STRIKE: HES 8000 x 801 x US32D

CARD READER: by others
CLOSER: LCN 1450

WALL BUMPER: HAGER 236W 626 FLUSH BOLT: Ives FB31P x US32D

COORDINATOR: Ives COR52 x FL20 coordinator w/ filler bar x 600 finish



GROUP 05:

TOP/BOTTOM OFFSET PIVOT: PER MANUFACTURER
CONCEALED OVERHEAD CLOSER: PER MANUFACTURER
CONCEALED ROD EXIT DEVICE: Sim. Von Duprin 99L Series

ELECTRIC STRIKE: HES 9600 x US32D

CARD READER: by others
ADA AUTO OPERATOR: Per contractor

THRESHOLD: PEMKO

DOOR BOTTOM: PEMKO 315CN WEATHERSTRIP: PEMKO 303AS



EXHIBIT E

MEDICAL EQUIPMENT



Type	<u>Item</u>	<u>Qtv</u>
Full Body Digital Xray	Vetray	1
Digital Dental Xray	Vetpro Digital Dental Xray with Progeny Software and Laptop 76"	1
Surgery Lights	MI 1000 Dual Ceiling Light	2
Treatment Lights	MI 750 Ceiling Lights	4
Mobile Anesthesia Machines	VMS Plus with Vaporizer-Midmark	3
Wall Mount Anesthesia Machines	VMS Wall Mount Anesthesia Machines-Midmark	4
Dental Lift Table	Canis Major Wet Exam Table-Midmark	1
Dental Machine	Vetpro 1000	1
Mobile Lift	061770-Olympic Versa Lift 3 in 1 W/Stretchers	1
Monitors	Midmark Insight w NIBP, SPO2	7
Surgery Tables	Surgery Tables Flat Top/Heat/Hydraulic-VSSI	2
Cat Scale	Table Top LCD-VSSI	1
Floor Scale	Platform Scale VSSI	1
Fold Up Exam Tables	Fold Up Wall Mount Exam Tables-VSSI	2
Scrub Sink with Foot Pedal	Single Surgeon's Scrub Sink w Faucet and Pedal	1
Autoclave	M11 Midmark	1
Washer	LG Commercial Stackable Washer	1
Dryer	LG Commercial Stackable Dryer Electric	1
Centrifuge	068686 E8 Centrifuge Jorgensen	1
Scavenger	Gas-Vak Multi-Station Unit for up to 12 drops	1
Scavenger	Gas-Vak Atmospheric Equilizer	4
Scavenger	Gas-Vak Wall Mount Balancing valve	4
Surgical Instrument Trays	004288-Mayo Stands	2
Narcotic Safe	022622 Narcotic Cabinet 24x30x10	1



EXHIBIT F

MISC. CONTAINMENT




Item	QTY	Room	Manufacturer
K9 Cabins - Single Row Type- Double Stacked System - consisting of, (2) 3' wide x 3' deep Runs, (4) 4' wide x 3' deep Runs, with Glass Gates, with Rideboard Floors, Stainless Steel over Polycore Panels, with Back Panels, with End Panels, with Silvis Seals, no Drains, with Stainless Steel 3 in. Grid Top Covers E110.	1	E110	Mason/Midmark
K9 Cabins - Single Row Type- Double Stacked System - consisting of, (4) 3' wide x 3' deep Runs, (2) 4' wide x 3' deep Runs, with Glass Gates, with Rideboard Floors, Stainless Steel over Polycore Panels, with Back Panels, with End Panels, with Silvis Seals, no Drains, with Stainless Steel 3 in. Grid Top Covers A120/132-10' SECTION. TO BE 30" DEEP	2	A120 / A132	Mason/Midmark
K9 Cabins - Single Row Type- Double Stacked System - consisting of, (2) 3' wide x 3' deep Runs, (6) 4' wide x 3' deep Runs, with Glass Gates, with Rideboard Floors, Stainless Steel over Polycore Panels, with Back Panels, with End Panels, with Silvis Seals, no Drains, with Stainless Steel 3 in. Grid Top Covers A120/132-11' SECTION. TO BE 30" DEEP	2	A120 / A132	Mason/Midmark
K9 Cabins - Single Row Type- Double Stacked System - consisting of, (4) 3' wide x 3' deep Runs, (4) 4' wide x 3' deep Runs, with Glass Gates, with Rideboard Floors, Stainless Steel over Polycore Panels, with Back Panels, with End Panels, with Silvis Seals, no Drains, with Stainless Steel 3 in. Grid Top Covers A103-14'-8 3/4" SECTION	1	A103	Mason/Midmark
K9 Cabins - Single Row Type- Double Stacked System - consisting of, (8) 4' wide x 3' deep Runs, with Glass Gates, with Rideboard Floors, Stainless Steel over Polycore Panels, with Back Panels, with End Panels, with Silvis Seals, no Drains, with Stainless Steel 3 in. Grid Top Covers A103-16' SECTION. TO BE 30" DEEP	1	A103	Mason/Midmark
K9 Cabins - Single Row Type- Double Stacked System - consisting of, (10) 3' wide x 3' deep Runs, with Glass Gates, with Rideboard Floors, Stainless Steel over Panels, with Back Panels, with End Panels, with Silvis Seals, no Drains, with Stainless Steel 3 in. Grid Top Covers A103-15'-5 1/2" SECTION. TO BE 30" DEEP	1	A103	Mason/Midmark




K9 Cabins - Single Row Type- Double Stacked System - consisting of, (4) 4' wide x 3' deep Runs, with Glass Gates, with Rideboard Floors, Stainless Steel over Polycore Panels, with Back Panels, with End Panels, with Silvis Seals, no Drains, with Stainless Steel 3 in. Grid Top Covers A103-8' SECTION. TO BE 30" DEEP	1	A103	Mason/Midmark
K9 Cabins - Single Row Type- Double Stacked System - consisting of, (10) 3' wide x 3' deep Runs, (2) 4' wide x 3' deep Runs, with Glass Gates, with RideboardFloors, Stainless Steel over Polycore Panels, with BackPanels, with End Panels, with Silvis Seals, no Drains, with Stainless Steel 3 in. Grid Top Covers A103-19' SECTION. TO BE 30" DEEP	1	A103	Mason/Midmark
See following pages for description of item.	1	A109	Midmark
See following pages for description of item.	1	A123	Midmark
See following pages for description of item.	1	A125	Midmark
See following pages for description of item.	1	A134	Midmark
See following pages for description of item.		A144	Midmark
See following pages for description of item.		E106	Midmark
See following pages for description of item.	1	E115	Midmark































EXHIBIT G

LOW VOLTAGE RESPONSIBILITIES



SCOPE OF WORK CHECKLIST

Responsibility Matrix

KEY / LEGEND

Owner/End-User: OWN
Electrical Contractor: EC
Integrated Electronics: IE
By Other Trade or Not Applicable: OT or N/A

DESCRIPTION	SUPPLY	INSTALL	SUPPORT/ WARANTY	COMMENTS
DESIGN BUILD - ELECTRICAL				
General Electrical				
all Electrical Power Service (120V, 220V, etc.)	EC	EC	EC	
Access Control System Back Boxes & Rough-in				
Access Control Head-End MDF/IDF Specialty Electrical Backboxes	OWN	EC	OWN	OWN supplied EC Installed
ccess Control Field/Remote Located Specialty Electrical Backboxes	OWN	EC	OWN	OWN supplied EC Installed
ccess Control Junction Boxes & Gutter Enclosures	EC	EC	EC	
ccess Control Electrical Fittings, Couplers, etc.	EC	EC	EC	
access Control Field Device Non-Specialty Backboxes	EC	EC	EC	EC provided
ire Alarm System Back Boxes & Rough-in				
ire Alarm Head-End MDF/IDF Specialty Electrical Backboxes	IE	EC	IE	IE supplied EC Installed
ire Alarm Field/Remote Located Specialty Electrical Backboxes	IE	EC	IE	IE supplied EC Installed
ire Alarm Junction Boxes & Gutter Enclosures	EC	EC	EC	
ire Alarm Electrical Fittings, Couplers, etc.	EC	EC	EC	
ire Alarm Field Device Non-Specialty Backboxes	EC	EC	EC	EC provided
ntrusion Detection System Back Boxes & Rough-in				
ntrusion Detection Head-End MDF/IDF Specialty Electrical Backboxes	IE	EC	IE	IE supplied EC Installed
ntrusion Detection Field/Remote Located Specialty Electrical Backboxes	IE	EC	IE	IE supplied EC Installed
ntrusion Detection Junction Boxes & Gutter Enclosures	EC	EC	EC	
ntrusion Detection Electrical Fittings, Couplers, etc.	EC	EC	EC	
ntrusion Detection Field Device Non-Specialty Backboxes	EC	EC	EC	EC provided
Public Address System Back Boxes & Rough-in				
ublic Address Head-End MDF/IDF Specialty Electrical Backboxes	IE	EC	IE	IE supplied EC Installed
rublic Address Field/Remote Located Specialty Electrical Backboxes	IE	EC	IE	IE supplied EC Installed
ublic Address Junction Boxes & Gutter Enclosures	EC	EC	EC	
rublic Address Electrical Fittings, Couplers, etc.	EC	EC	EC	
rublic Address Field Device Non-Specialty Backboxes	EC	EC	EC	EC provided
structured Cabling System Back Boxes & Rough-in				
tructured Cabling Head-End MDF/IDF Specialty Electrical Backboxes	iΕ	EC	IE	IE supplied EC Installed
tructured Cabling Field/Remote Located Specialty Electrical Backboxes	IE	EC	1E	IE supplied EC Installed
tructured Cabling Junction Boxes & Gutter Enclosures	EC	EC	EC	
tructured Cabling Electrical Fittings, Couplers, etc.	EC	EC	EC	
tructured Cabling Field Device Non-Specialty Backboxes	EC	EC	EC	EC provided
/ideo Surveillance System Back Boxes & Rough-in				
ideo Surveillance Head-End MDF/IDF Specialty Electrical Backboxes	OWN	EC	OWN	OWN supplied EC Installed
ideo Surveillance Field/Remote Located Specialty Electrical Backboxes	OWN	EC	OWN	OWN supplied EC Installed
/ideo Surveillance Junction Boxes & Gutter Enclosures	EC	EC	EC	

9427 - Fresno Animal Control Facility Scope of Work Letter REV1



DESCRIPTION	SUPPLY	INSTALL	SUPPORT/ WARANTY	COMMENTS
rideo Surveillance Electrical Fittings, Couplers, etc.	EC	EC	EC	
rideo Surveillance Field Device Non-Specialty Backboxes	EC	EC	EC	EC provided
Cable Pathways				
lectrical Conduit (RMC, GRC, IMC, EMT, PVC, FRE, RTRC, RNC, ENT)	EC	EC	EC	
lexible Electrical Conduit (FMC, Flex, LFMC, FMT, LFNC)	EC	EC	EC	
Inderground Cable Pathways	EC	EC	EC	
urface Mounted Raceway (Wire Molding)	EC	EC	EC	
unction Box and Gutter Enclosures	EC	EC	EC	
lectrical Fittings, Couplers, Bushings, & Bodies	EC	EC	EC	
irestopping; Firewall Penetrations, Sleeves, & Caulking, etc.	EC	EC	EC	
Inistrut & Threaded Rods	EC	EC	EC	
erminal Cabinets	EC	EC	EC	
Vire Basket & Cable Tray	N/A	N/A	N/A	Not Applicable
Prop Tile Ceiling Wires & Fasteners	от	ОТ	ОТ	Other Trade provided
ccess Hatches	N/A	N/A	N/A	Not Applicable
DESIGN BUILD - COMMUNICATIONS				
Public Address				
ublic Address System Design	ΙE	ΙE	IE	
ublic Address System Server	N/A	N/A	N/A	Not Applicable
ublic Address System Client Workstations	N/A	N/A	N/A	Not Applicable
ublic Address System Local UPS Equipment	N/A	N/A	N/A	Not Applicable
ublic Address System Software & Licensing	N/A	N/A	N/A	Not Applicable
Controller Head-End MDF/IDF Equipment	IE	IE	IE .	
Controller Head-End MDF/IDF Equipment Back-up Batteries	ΙE	ΙE	IE.	
Controller Head-End MDF/IDF Connections	ΙE	IE	IE .	
Optional) Controller Field/Remote Located Equipment	N/A	N/A	N/A	Not Applicable
Optional) Controller Field/Remote Located Equipment Back-up Batteries	N/A	N/A	N/A	Not Applicable
Optional) Controller Field/Remote Located Connections	N/A	N/A	N/A	Not Applicable
peakers	IE	IE	IE	
peaker Connections	ΙE	IE	IE	
ublic Address System Low Voltage Cable	ΙE	IE	IE	
ublic Address System Low Voltage Cable Connections	IE	IE	IE	
rublic Address System Low Voltage Cable Support J-Hooks & Hangers	IE	IE	IE	
Prop Tile Ceiling Wires & Fasteners	ОТ	ОТ	ОТ	Other Trade provided
rublic Address System Programming	IE	IE	IE	
inal System Testing & Comissioning w/A.H.J.	IE	IE	IE	
ind-User Orientation & Training	IE	IE	IE	
Operation & Maintenance Manuals	ΙE	IE	ΙE	
PI/Integration with Periphereal Systems or Products	N/A	N/A	N/A	Not Applicable
itructured Cabling				
tructured Cabling System Design	IE	IE	IE	
active Network Components	OWN	OWN	OWN	Owner provided
letwork Servers	OWN	OWN	OWN	Owner provided
letwork Switches & SFP Modules	OWN	OWN	OWN	Owner provided
letwork Patch Cables in MDF's & IDF's	OWN	OWN	OWN	Owner provided
T. Computer Systems & Software Equipment	OWN	OWN	OWN	Owner provided

9427 - Fresno Animal Control Facility Scope of Work Letter REV1



DESCRIPTION	SUPPLY	INSTALL	SUPPORT/ WARANTY	COMMENTS
Computers and Equipment	OWN	OWN	OWN	Owner provided
Computer and Equipment Connections	OWN	OWN	OWN	Owner provided
Monitors, Consoles, & Workstations	OWN	OWN	OWN	Owner provided
Network Patch Cables at Workstation & Furniture Locations	OWN	OWN	OWN	Owner provided
Wireless Bridge Networking Equipment	OWN	OWN	OWN	Owner provided
Wireless Bridge Networking Connections	OWN	OWN	OWN	Owner provided
Owner Wifi, Public/Guest Wifi, Cell Phone Signal Boost	OWN	OWN	OWN	Owner provided
ocal UPS Equipment	OWN	OWN	OWN	Owner provided
MDF & IDF Racks & Cabinets	IE	ΙE	IE	
MDF & IDF Rack & Cabinet Wire Management	IE	IE	IE	
MDF & IDF Racks & Cabinets Grounding & Bonding	IE	IE	IE.	
MDF & IDF Cable Ladder Rack	IE	IE	IE	
MDF & IDF Fire-Rated Plywood Backboards	IE	IE	IE .	
Patch Panels	IE	IE	IE	
Patch Panel Connectors & Modules	IE	IE	IE IE	
Patch Panel Connector & Module Connections	IE	IE	IE	
CATSe / CAT6 / CAT6A Cable	IE	IE	IE .	
CATSe / CAT6 / CAT6A Cable Connections	IE	IE	IE	
CATSe / CAT6 / CAT6A Cable Support J-Hooks & Hangers	IE	IE.	IE .	
Fiber Optic Cable	N/A	N/A	N/A	Not Applicable
Fiber Optic Cable connections	N/A	N/A	N/A	Not Applicable
Fiber Optic Cable Support J-Hooks & Hangers	N/A	N/A	N/A	Not Applicable
Multi-Pair Analog Cable	N/A	N/A	N/A	Not Applicable
Multi-Pair Analog Cable Connections	N/A	N/A	N/A	Not Applicable
Multi-Pair Analog Cable Support J-Hooks & Hangers	N/A	N/A	N/A	Not Applicable
Orop Tile Ceiling Wires & Fasteners	от	ОТ	OT	Other Trade provided
Connectors, Modules, & Faceplates	IE.	IE.	IE .	Other Hade provided
Connectors, Modules, & Faceplate Connections	IE	IE	IE	
Cable & Faceplate Labeling	IE IE	IE.	IE IE	
Jtility/Service Provider Coordination Final Connection	ОТ	OT	OT	Other Trade provided
MPOE Final Connection	от	от	ОТ	Other Trade provided
Final System Testing & Comissioning w/A.H.J.	IE	IE	IE	Other Trade provided
Operation & Maintenance Manuals	IE	IE	IE	
DESIGN BUILD - ELECTRONIC SAFETY & SECURITY	IE	IL	IL	
Access Control				_
and the same and t	Own	OWN	OWN	
Access Control System Design Access Control System Server		OWN	OWN	
Access Control System Server Access Control System Client Workstations	OWN	OWN	OWN	
	OWN	OWN	OWN	
Access Control System Monitors & Consoles	OWN		OWN	
Access Control System Local UPS Equipment		OWN		
Access Control System Software & Licensing	OWN	OWN	OWN	
Credentials (Cards, Fobs, NFC, Bluetooth, etc.)	OWN	OWN	OWN	
Badge Printer (Credential Printer) & Consumables	OWN	OWN	OWN	
Controller Head-End MDF/IDF Equipment	OWN	OWN	OWN	
Controller Head-End MDF/IDF Equipment Back-up Batteries	OWN	OWN	OWN	Own to terminate cable & make final conn

9427 - Fresno Animal Control Facility Scope of Work Letter REV1



DESCRIPTION	SUPPLY	INSTALL	SUPPORT/ WARANTY	COMMENTS
(Optional) Controller Field/Remote Located Equipment	OWN	OWN	OWN	
(Optional) Controller Field/Remote Located Equipment Back-up Batteries	OWN	OWN	OWN	
(Optional) Controller Field/Remote Located Connections	OWN	OWN	OWN	Own to terreinate cable & make final connection
Door Card Readers	OWN	OWN	OWN	
Door Card Reader Connections	OWN	OWN	OWN	Own to terminate cable & make final connection
Door Contacts & Door Position Switches	OWN	OWN	OWN	
Door Contact & Door Position Switch Connections	OWN	OWN	OWN	Own to terminate cable & make final connection
Door Request-to-Exit & Push-to-Exit Devices	OWN	own	OWN	
Door Request-to-Exit & Push-to-Exit Device Connections	OWN	OWN	OWN	Own to terminate cable & make final connection
Door Remote Release Buttons	OWN	OWN	OWN	
Door Remote Release Button Connections	OWN	OWN	OWN	Own to terminate cable & make final connection
12/24V Door Hardware & Magnetic Locking Hardware	от	ОТ	от	Other Trade provided
12/24V Door Hardware & Magnetic Locking Hardware Connections	OWN	OWN	OWN	Owner provided
12/24V Door Hardware & Magnetic Locking Hardware Power Supplies	own	OWN	OWN	Owner provided
Storefront Door Electrified Locking & Magnetic Hardware	OT	ОТ	OT	Other Trade provided
Storefront Door Electrified Locking & Magnetic Hardware Connections	OWN	OWN	OWN	Owner provided
Storefront Door Electrified Locking & Magnetic Hardware Power Supplies	ОТ	ОТ	ОТ	Other Trade provided
Actuator & Automatic Door Operator Interface	own	own	OWN	Owner provided
ADA Handicap Buttons & Accessibility Equipment Interface	N/A	N/A	N/A	Not Applicable
Turnstile & Pedestrian Gate Controller Interface	N/A	N/A	N/A	Not Applicable
Vehicle Gate Controller Interface	N/A	N/A	N/A	Not Applicable
Access Control System Low Voltage Cable	ΙE	ΙE	1E	
Access Control System Low Voltage Cable Connections	OWN	OWN	OWN	Own to terminate cable & make final connections
Access Control System Low Voltage Cable Support J-Hooks & Hangers	IΕ	ΙE	IE	
Drop Tile Ceiling Wires & Fasteners	ОТ	от	OT	Other Trade provided
Access Control System Programming	OWN	OWN	OWN	
Final System Testing & Comissioning w/A.H.J.	OWN	OWN	OWN	
End-User Orientation & Training	OWN	OWN	OWN	
Web & App Based Remote Services	OWN	OWN	OWN	
Operation & Maintenance Manuals	OWN	OWN	OWN	
API/Integration with Periphereal Systems or Products	OWN	OWN	OWN	
Fire Alarm				
Fire Alarm System Design	IE	IE	IE	
Fire Alarm System Control Server	N/A	N/A	N/A	Not Applicable
Fire Alarm System Control Client Workstations	N/A	N/A	N/A	Not Applicable
Fire Alarm System Monitors & Consoles	N/A	N/A	N/A	Not Applicable
Fire Alarm System Local UPS Equipment	N/A	N/A	N/A	Not Applicable
Fire Alarm System Software & Licensing	N/A	N/A	N/A	Not Applicable
Fire Alarm Control Unit (FACU) Head-End MDF/IDF Equipment	IE	IE	IE	
Fire Alarm Control Unit (FACU) Head-End MDF/IDF Back-up Batteries	IE	IE	IE	
Fire Alarm Control Unit (FACU) Head-End MDF/IDF Connections	IE	IE	IE	
(Optional) Controller Field/Remote Located Equipment	IE	IE	IE	
(Optional) Controller Field/Remote Located Equipment Back-up Batteries	IE	IE	ΙE	
(Optional) Controller Field/Remote Located Connections	IE	IE	IE	
Voice Evacuation Equipment	N/A	N/A	N/A	Not Applicable
Voice Evacuation Connections	N/A	N/A	N/A	Not Applicable

9427 - Fresno Animal Control Facility Scope of Work Letter REV1



DESCRIPTION	SUPPLY	INSTALL	SUPPORT/ WARANTY	COMMENTS
Mass Notification Equipment	N/A	N/A	N/A	Not Applicable
flass Notification Connections	N/A	N/A	N/A	Not Applicable
istributed Antenna System (DAS) Equipment	N/A	N/A	N/A	Not Applicable
istributed Antenna System (DAS) Connections	N/A	N/A	N/A	Not Applicable
i-Directional Antenna (BDA) Equipment	N/A	N/A	N/A	Not Applicable
i-Directional Antenna (BDA) Connections	N/A	N/A	N/A	Not Applicable
rea-of-Refuge Equipment	N/A	N/A	N/A	Not Applicable
rea-of-Refuge Connections	N/A	N/A	N/A	Not Applicable
wo-Way Communication Equipment	N/A	N/A	N/A	Not Applicable
wo-Way Communication Connections	N/A	N/A	N/A	Not Applicable
elayed Egress Interface Equipment	N/A	N/A	N/A	Not Applicable
elayed Egress Interface Connections	N/A	N/A	N/A	Not Applicable
ire Supression System Equipment	OT	ОТ	ОТ	Other Trade provided
ire Supression System Connections	ОТ	ОТ	ОТ	Other Trade provided
ire Alarm System Related Fire Suppression Interface Equipment	N/A	N/A	N/A	Not Applicable
ire Alarm System Related Fire Suppression Interface Connections	N/A	N/A	N/A	Not Applicable
ire Smoke Control System Equipment	OT	от	ОТ	Other Trade provided
ire Smoke Control System Connections	ОТ	ОТ	ОТ	Other Trade provided
ire Alarm System Related Fire Smoke Control Interface Equipment	N/A	N/A	N/A	Not Applicable
ire Alarm System Related Fire Smoke Control Interface Connections	N/A	N/A	N/A	Not Applicable
ire Alarm System Annunciators	IE	IE	IE	
ire Alarm System Network Annunciators	N/A	N/A	N/A	Not Applicable
ire Alarm System Graphic Annunciators	N/A	N/A	N/A	Not Applicable
ire Alarm System Remote Power Supplies	1E	IE	IE	
ire Alarm System Remote Power Supply Back-up Batteries	1E	IΕ	IE.	
ire Alarm System Remote Power Supply Connections	IE	IE	1E	
nitiating Devices	1E	IE	1E	
nitiating Device Connections	IE	IE	1E	
arbon Monoxide (Detectors, Alarms, etc.)	N/A	N/A	N/A	Not Applicable
20V Smoke Detectors	N/A	N/A	N/A	Not Applicable
lotification Appliances	IE	IE	IE	
lotification Appliance Connections	IE	IE	IE	
peakers	N/A	N/A	N/A	Not Applicable
peaker Connections	N/A	N/A	N/A	Not Applicable
himes	N/A	N/A	N/A	Not Applicable
hime Connections	N/A	N/A	N/A	Not Applicable
ire Alarm System Duct Detectors	IE	IE	IE	
VAC System Duct Detectors	ОТ	ОТ	ОТ	Other Trade provided
ire Alarm System Duct Detector Monitor Module	IE.	IE	IE	
ire Alarm System Duct Detector Monitor Module Connection	IE	IE	IE	
ire Smoke Damper Equipment	ОТ	ОТ	ОТ	Other Trade provided
ire Smoke Damper Connections	OT	ОТ	ОТ	Other Trade provided
ire Alarm System Related Fire Smoke Damper Interface Equipment	IE	IE	IE	
ire Alarm System Related Fire Smoke Damper Interface Connections	IE	IE	IE	
fagnetic Door Holder; 12/24V	IE	IE	IE	
and the second s		_ ~		

9427 - Fresno Animal Control Facility Scope of Work Letter REV1



DESCRIPTION	SUPPLY	INSTALL	SUPPORT/ WARANTY	COMMENTS
Magnetic Door Holder; 120V	N/A	N/A	N/A	Not Applicable
Magnetic Door Holder; 120V Connections	N/A	N/A	N/A	Not Applicable
Elevator Recall Equipment	от	от	OT	Other Trade provided
Elevator Recall Connections	OT	OT	OT	Other Trade provided
Fire Alarm System Related Elevator Recall Interface Equipment	N/A	N/A	N/A	Not Applicable
Fire Alarm System Related Elevator Recall Interface Connections	N/A	N/A	N/A	Not Applicable
Elevator Shunt-Trip Equipment	OT	OT	OT	Other Trade provided
Elevator Shunt-Trip Connections	OT	ОТ	OT	Other Trade provided
Fire Alarm System Related Elevator Shunt-Trip Interface Equipment	N/A	N/A	N/A	Not Applicable
Fire Alarm System Related Elevator Shunt-Trip Interface Connections	N/A	N/A	N/A	Not Applicable
Fire Sprinkler System Equipment	ОТ	от	ОТ	Other Trade provided
Fire Sprinkler System Connections	ОТ	ОТ	OT	Other Trade provided
Fire Alarm System Related Fire Sprinkler Interface Equipment	IE.	IE.	IE	
Fire Alarm System Related Fire Sprinkler Interface Connections	IE	IE	IE	
Fire Sprinkler System Water-Flow Switches	ОТ	ОТ	от	Other Trade provided
Fire Alarm System Water-Flow Switch Monitor Module	IE	IE	IE	
Fire Alarm System Water-Flow Switch Monitor Module Connection	IE	IE	IE	
Fire Sprinkler System Tamper Switches	ОТ	от	ОТ	Other Trade provided
Fire Alarm System Tamper Switch Monitor Module	IE	IE	IE	
Fire Alarm System Tamper Switch Monitor Module Connection	IE	IE	IE	
Fire Sprinkler System P.I.V. Tamper Switches	ОТ	ОТ	OT	Other Trade provided
Fire Alarm System P.I.V. Tamper Switch Monitor Module	IE	IE	IE	outer France provided
Fire Alarm System P.I.V. Tamper Switch Monitor Module Connection	IE	IE.	IE IE	
Fire Sprinkler System O.S.&.Y. Tamper Switches	от	от	OT	Other Trade provided
Fire Alarm System O.S.&.Y.Tamper Switch Monitor Module	IE.	IE.	IF.	other frage provides
Fire Alarm System O.S.&.Y. Tamper Switch Monitor Module Connection	IE.	IE	IE	
Fire Sprinkler System Fire Pump Equipment	OT	OT	OT	Other Trade provided
Fire Sprinkler System Fire Pump Connections	OT	от	OT	Other Trade provided
Fire Alarm System Related Fire Sprinkler Pump Interface Equipment	N/A	N/A	N/A	Not Applicable
Fire Alarm System Related Fire Sprinkler Pump Interface Connections	N/A	N/A	N/A	Not Applicable
Fire Sprinkler System Bell	ОТ	ОТ	OT	Other Trade provided
Fire Alarm Low Voltage Cable	IE	IE	IE	Other Frade provided
Fire Alarm Low Voltage Cable Connections	IE	IE	IF.	
Fire Alarm Low Voltage Cable Support J-Hooks & Hangers	IE.	IE.	IE.	
Drop Tile Ceiling Wires & Fasteners	от	ОТ	OT	Other Trade provided
Fire Alarm System Programming	IE	IE	IE .	Other frade provided
Final System Testing & Comissioning w/A.H.J.	IE.	IE.	IE IE	
End-User Orientation & Training	IE.	IE IE	IE IE	
Web & App Based Remote Services	N/A	N/A	N/A	Not Applicable
Permitting	IE.	IE IE	IE.	not Applicable
UL Central Station Monitoring Service	N/A	N/A	N/A	Not Applicable
UL Fire Alarm Service Certification	N/A	N/A	N/A	Not Applicable
API/Integration with Periphereal Systems or Products	N/A N/A	N/A N/A	N/A N/A	Not Applicable
Intrusion Detection	N/A	N/A	N/A	NOL Applicable
Intrusion Detection Intrusion Detection System Design	IE	IE	IE	
				Not Applicable
Intrusion Detection System Server	N/A	N/A	N/A	Not Applicable

9427 - Fresno Animal Control Facility Scope of Work Letter REV1



DESCRIPTION	SUPPLY	INSTALL	SUPPORT/ WARANTY	COMMENTS
ntrusion Detection System Client Workstations	N/A	N/A	N/A	Not Applicable
ntrusion Detection System Monitors & Consoles	N/A	N/A	N/A	Not Applicable
ntrusion Detection System Local UPS Equipment	N/A	N/A	N/A	Not Applicable
ntrusion Detection System Software & Licensing	N/A	N/A	N/A	Not Applicable
Controller Head-End MDF/IDF Equipment	ΙE	IE	ΙE	
Controller Head-End MDF/IDF Back-up Batteries	IE	IE	IE	
Controller Head-End MDF/IDF Connections	IE	IE	IE	
Optional) Controller Field/Remote Located Equipment	IE	IE	IE	
Optional) Controller Field/Remote Located Equipment Back-up Batteries	IE	IE	IE	
Optional) Controller Field/Remote Located Connections	IE	IE	IE	
eypads	IΕ	IE	IΕ	
eypad Connections	IΕ	IE	IE	
Door Contacts & Door Position Switches	IΕ	IE	IE.	
Poor Contact & Door Position Switch Connections	IE	IE	IE	
Motion Detectors	IE	IE	IE	
Action Detector Connections	IE	IE	IE	
Glass Break Detectors	N/A	N/A	N/A	Not Applicable
Glass Break Detector Connections	N/A	N/A	N/A	Not Applicable
Vireless Sensors & Detectors	N/A	N/A	N/A	Not Applicable
Vireless Sensor & Detector Connections	N/A	N/A	N/A	Not Applicable
pecial Application Sensors & Detectors	N/A	N/A	N/A	Not Applicable
pecial Application Sensor & Detector Connections	N/A	N/A	N/A	Not Applicable
ife Safety Sensors & Detectors	N/A	N/A	N/A	Not Applicable
ife Safety Sensor & Detector Connections	N/A	N/A	N/A	Not Applicable
ounding & Strobe Devices	IE	IE	IE	
ounding & Strobe Device Connections	IE	IE	IE	
ntrusion Detection System Low Voltage Cable	IE	IE	IE	
ntrusion Detection System Low Voltage Cable Connections	IE	IE	1E	
ntrusion Detection System Low Voltage Cable Support J-Hooks & Hangers	IE	IE	IE	
Prop Tile Ceiling Wires & Fasteners	ОТ	ОТ	ОТ	Other Trade provided
ntrusion Detection System Programming	IE	IE	IE	
inal System Testing & Comissioning w/A.H.J.	IE	IE	IE	
ind-User Orientation & Training	IE	IE	IE	
Veb & App Based Remote Services	N/A	N/A	N/A	Not Applicable
JL Central Station Monitoring Service	IE.	IE	IE	
API/Integration with Periphereal Systems or Products	N/A	N/A	N/A	Not Applicable
/ideo Surveillance				
ideo Surveillance System Design	OWN	own	OWN	
ideo Surveillance System Network video Recorder (NVR)	OWN	OWN	OWN	
ideo Surveillance System Client Workstations	OWN	OWN	OWN	
/ideo Surveillance System Monitors & Consoles	OWN	OWN	OWN	
ideo Surveillance System Local UPS Equipment	OWN	OWN	OWN	
ideo Surveillance System Software & Licensing	OWN	OWN	OWN	
ideo Surveillance System Head-End MDF/IDF Equipment	OWN	OWN	OWN	
rideo Surveillance System Head-End MDF/IDF Connections	OWN	OWN	OWN	Own to terminate cable & make final connec
rideo Surveillance System Head-End MDF/IDF Local UPS Equipment	OWN	OWN	OWN	

9427 - Fresno Animal Control Facility Scope of Work Letter REV1



DESCRIPTION	SUPPLY	INSTALL	SUPPORT/ WARANTY	COMMENTS
(Optional) Controller Field/Remote Located Equipment	OWN	OWN	OWN	
(Optional) Controller Field/Remote Located Equipment Back-up Batteries	OWN	OWN	OWN	
(Optional) Controller Field/Remote Located Connections	OWN	OWN	OWN	Own to terminate cable & make final connections
Long Distance Video Signal Transmission Equipment	OWN	OWN	OWN	
Long Distance Video Signal Transmission Equipment Back-up Batteries	OWN	OWN	OWN	
Long Distance Video Signal Transmission Connections	OWN	OWN	OWN	Own to terminate cable & make final connections
Wireless Bridge Networking Equipment	OWN	OWN	OWN	
Wireless Bridge Networking Connections	OWN	OWN	OWN	Own to terminate cable & make final connections
Network Switches & SFP Modules	OWN	OWN	OWN	
Network Patch Cables in MDF's & IDF's	OWN	OWN	OWN	Own to terminate cable & make final connections
Power-over-Ethernet (PoE, PoE+, & PoE++)	OWN	OWN	OWN	
Cameras - Site	OWN	OWN	OWN	
Cameras - Interior	OWN	OWN	OWN	
Cameras - Exterior	OWN	OWN	OWN	
Camera Connections	OWN	OWN	OWN	Own to terminate cable & make final connections
Camera Mounting Hardware	OWN	OWN	OWN	
Network Patch Cables at Camera Locations	OWN	OWN	OWN	Own to terminate cable & make final connections
Camera Power Supply Equipment	OWN	OWN	OWN	
Camera Power Supply Back-up Batteries	OWN	OWN	OWN	
Camera Power Supply Connections	OWN	OWN	OWN	Own to terminate cable & make final connections
Video Surveillance System Low Voltage Cable	IE	IE	IE	
Video Surveillance System Low Voltage Cable Connections	OWN	OWN	OWN	Own to terminate cable & make final connections
Video Surveillance System Low Voltage Cable Support J-Hooks & Hangers	IE	IE	IE	
Drop Tile Ceiling Wires & Fasteners	OT	ОТ	OT	
Video Surveillance System Programming	OWN	OWN	OWN	
Final System Testing & Comissioning w/A.H.J.	OWN	OWN	OWN	
End-User Orientation & Training	OWN	OWN	OWN	
Web & App Based Remote Services	OWN	OWN	OWN	
API/Integration with Periphereal Systems or Products	OWN	OWN	OWN	


9427 - Fresno Animal Control Facility Scope of Work Letter REV1




EXHIBIT H

CAMERA WIRING LOCATIONS









































EXHIBIT I

ISD ELECTRICAL COMMENTS



