



GENERAL NOTES

- 1. CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND EXISTING CONDITIONS PRIOR TO THE START OF WORK. NOTIFY THE ARCHITECT OF ANY SIGNIFICANT CHANGES IN DIMENSIONS OR CONDITIONS.
- 2. THE CONTRACTOR SHALL PROVIDE ALL MATERIALS, TOOLS, EQUIPMENT AND NECESSARY FACILITIES, AND PERFORM ALL LABOR AND SERVICES OF EVERY DESCRIPTION AS MAY BE NECESSARY TO COMPLETE THE SCOPE OF WORK DEFINED ON THE DRAWINGS.
- 3. THE CONTRACTOR SHALL ARRANGE FOR, OBTAIN AND PAY FOR ALL PERMITS, CERTIFICATES, INSPECTIONS, AGENCY APPROVALS, ETC. AND PAY ALL FEES LEVIED BY STATE, LOCAL AND MUNICIPAL AUTHORITIES HAVING JURISDICTION OVER WORK PERFORMED UNDER THIS CONTRACT. PROVIDE COPIES OF ALL REQUIRED PERMITS, CERTIFICATES, INSPECTIONS AND AGENCY APPROVALS TO THE OWNER.
- 4. FABRICATE AND INSTALL ALL WORK IN STRICT ACCORDANCE WITH THE CBC, ALL APPLICABLE STATE AND LOCAL CODES.
- 5. ALL CONTRACTORS AND SUBCONTRACTORS SHALL BE RESPONSIBLE FOR THE PROPER PERFORMANCE OF THEIR WORK, COORDINATING WITH OTHER TRADES, MEANS AND METHODS OF CONSTRUCTION, SAFETY AND SECURITY
- 6. CUTTING AND PATCHING SHALL BE PERFORMED BY EACH TRADE AS NECESSARY FOR THE PERFORMANCE AND INSTALLATION OF THEIR WORK.

SALES AREA COUNTERS TO BE A DEFERRED SUBMITTAL BY

ADJACENT A WALKING SURFACE COMPLYING WITH 11B-403 (

ACCESSIBLE COUNTER WITH A 30"x48" CLEAR FLOOR AREA

2. SALES AREA COUNTERS (SERVICE COUNTERS) SHALL

ARRANGED FOR PARALLEL APPROACH PER CBC

COMPLY WITH CBC 11B-904 AND SHALL BE LOCATED

SALES AREA COUNTERS SHALL BE PROVIDED WITH AN

4. MAXIMUM HEIGHT OF THE ACCESSIBLE COUNTER IS 34" AFF (

THE ACCESSIBLE COUNTER SHALL EXTEND THE FULL

DEPTH OF THE SERVICE COUNTER AND SHALL BE A MINIMUM LENGTH OF 36" WITH 30"x48" CLEAR FLOOR AREA

OWNER/CONTRACTOR AS

11B-305.5(B)

PER CBC 11B-305.5(B)

- CUTTING AND PATCHING SHALL BE PERFORMED IN A WORKMANLIKE MANNER CONSISTENT WITH INDUSTRY STANDARDS FOR FINISHES AND SUBSTRATES AFFECTED. PATCHING OF EXISTING-TO-REMAIN WORK SHALL BE FINISHED TO MATCH ADJACENT CONSTRUCTION.
- 7. CONTRACTOR SHALL PROTECT THE FACILITY FROM WEATHER AND MAINTAIN SECURITY DURING ALL CONSTRUCTION WORK.
- 8. PROTECT EXISTING PROPERTY DURING CONSTRUCTION. REPAIR OR REPLACE, WITHOUT ADDITIONAL CHARGE TO THE OWNER, ANY EXISTING WORK DAMAGED DURING THE COURSE OF CONSTRUCTION.
- 9. THE WORK SHALL BE COORDINATED WITH THE PROJECT OWNER'S STAFF 10. UNLESS ITEMS OF MATERIAL, EQUIPMENT OR WORK ARE SPECIFICALLY NOTED TO BE PROVIDED OR FURNISHED BY OTHERS, THEY SHALL BE PROVIDED UNDER THIS CONTRACT.
- 11. MATERIALS AND COMPONENTS AS SPECIFIED CONSTITUTE A STANDARD OF QUALITY, UNLESS OTHERWISE NOTED. EQUAL SUBSTITUTES WILL BE ACCEPTABLE ONLY WITH WRITTEN PRIOR APPROVAL BY THE ARCHITECT.
- 12. ALL WORK SHALL BE PERFORMED BY SKILLED WORKERS IN A WORKMANLIKE AND PROFESSIONAL MANNER CONSISTENT WITH INDUSTRY STANDARDS.
- 13. REQUIRED EXITS, EXISTING STRUCTURAL ELEMENTS, FIRE PROTECTION DEVICES, AND SANITARY SAFEGUARDS SHALL BE MAINTAINED AT ALL TIMES DURING CONSTRUCTION.

ILLUMINATED AT ALL TIMES THAT THE ROOM OR SPACE SERVED BY THE

MEANS OF EGRESS IS OCCUPIED. THIS APPLIES TO LIGHTING OTHER THAN

PROVIDE EMERGENCY LIGHTING ON EXTERIOR LANDINGS AS REQUIRED BY

2022 CFC, SECTION 1010.1.6 FOR EXIT DOORWAYS THAT LEAD DIRECTLY TO

A SMOKE DETECTOR SHALL BE PROVIDED IN THE MAIN SUPPLY AIR DUCT OF

EACH HVAC UNIT TO SHUT OFF THE POWER SOURCE OF THE UNIT UPON THE

DETECTION OF SMOKE WHEN THE TOTAL CFM IN EXCESS OF 2000. 2022 CMC

PROVIDE ILLUMINATED EMERGENCY POWER PER CFC, SECTION 1008.3.2

THE MEANS OF EGRESS SERVING A ROOM OR SPACE, SHALL BE

THE EXIT SIGNS. 2022 CFC, SECTION 1008.2.

608.608.1

THE EXIT DISCHARGE. 2022 CFC, SECTION 1008.3.2

FINISH NOTES

OFFICE, IT, RECEPTION, & AREAS NOT INDICATED BELOW:

- 1. EXISTING GWB WALLS TO BE PRIMED AND PAINTED SHERWIN-WILLIAMS PROMAR ZERO VOC EG-SHEL LATEX (OR EQUAL), FINISH COLOR AS SELECTED
- EXISTING CEILING GRID TO REMAIN, REPLACE MISSING OR DAMAGED CEILING 3.
- 4. 4" BLACK RUBBER BASE OPTION 1: PROVIDE OPTION AT VENDOR ENTRANCE, PROCESSING, &
- CORRIDORS TO POLISH (E) CONCRETE FLOORING 6. OPTION 2: PROVIDE OPTION AT OFFICE FOR LOW MAINTENANCE COMMERCIAL

3. EPOXY FINISH EXISTING CONCRETE SLAB, COLOR AS SELECTED BY OWNER

SECURE STORAGE AREA:

CANNABIS BUSINESS ACTIVITY NOTE:

BUSINESS

BUILDING INTERIOR

NO CANNABIS CULTIVATION WILL BE CONDUCTED

ALL CANNABIS ACTIVITY LIMITED TO COMMERCIAL

ALL CANNABIS ACTIVITY WILL BE CONDUCTED WITHIN

NO CANNABIS OR CANNABIS PRODUCTS OR GRAPHICS

THE VEHICLES OWNED OR USED AS PART OF THE

DEPICTING CANNABIS OR CANNABIS PRODUCTS SHALL BE

VISIBLE FROM THE EXTERIOR OF ANY PROPERTY ISSUED A

COMMERCIAL CANNABIS BUSINESS PERMIT, OR ON ANY OF

CANNABIS RETAIL BUSINESS. NO OUTDOOR STORAGE OF

CANNABIS OR CANNABIS PRODUCTS IS PERMITTED AT ANY

- 1. GWB WALLS TO BE PRIMED AND PAINTED SHERWIN-WILLIAMS PROMAR ZERO VOC EG-SHEL LATEX (OR EQUAL), FINISH COLOR AS SELECTED BY OWNER
- EXISTING CEILING GRID TO REMAIN, REPLACE MISSING OR DAMAGED CEILING

CARPET TILE BY ARMSTRONG FLOORING, OR EQUAL

3. EPOXY FINISH EXISTING CONCRETE SLAB, COLOR AS SELECTED BY OWNER 4. 4" BLACK RUBBER BASE

- **BREAK ROOM:**
- 1. GWB WALLS TO BE PRIMED AND PAINTED SHERWIN-WILLIAMS PROMAR ZERO VOC EG-SHEL LATEX (OR EQUAL), FINISH COLOR AS SELECTED BY OWNER
- FLOOR FINISH TO BE LVT PLANK AS SELECTED BY OWNER EXISTING CEILING GRID TO REMAIN, REPLACE MISSING OR DAMAGED CEILING
- EPOXY FINISH EXISTING CONCRETE SLAB, COLOR AS SELECTED BY OWNER
- 4. 4" BLACK RUBBER BASE 7. OPTION 1: PROVIDE OPTION TO POLISH (E) CONCRETE FLOORING
- SALES ROOM, LOBBY, AND EXIT VESTIBULE, AND VENDOR ENTRANCE.
- 1. PROVIDE LEVEL 5 FINISH AT ALL SALES FLOOR WALLS, PATCH AND PAINT (E) WALLS WHERE REQUIRED 2. GWB WALLS TO BE PRIMED AND PAINTED SHERWIN-WILLIAMS PROMAR ZERO
- VOC EG-SHEL LATEX (OR EQUAL), FINISH COLOR AS SELECTED BY OWNER 3. COORDINATE WITH OWNER ON THE USE OF WALL DECALS/ MURALS/ WALLPAPER - WHERE REQUIRED, PROVIDE SUITABLE SUBSTRATE FOR
- MOUNTING 4. FLOOR FINISH TO BE LVT PLANK AS SELECTED BY OWNER
- 5. EXISTING CEILING GRID TO REMAIN, REPLACE MISSING OR DAMAGED CEILING TILES, PRIME & PAINT FULL CEILING (GRID AND TILES) SHERWIN-WILLIAMS PROMAR ZERO VOC FLAT LATEX (OR EQUAL), CEILING WHITE
- 4" BLACK VINYL COVE BASE 7. OPTION 1: PROVIDE OPTION TO POLISH (E) CONCRETE FLOORING

EXISTING TOILET ROOM(S):

- 1. WALLS TO BE PRIMED AND PAINTED SHERWIN-WILLIAMS PROMAR ZERO VOC SATIN LATEX (OR EQUAL), FINISH COLOR AS SELECTED BY OWNER. PROVIDE SMOOTH FINISH FRP TO 48" AFF ON WALLS, COLOR AS SELECTED BY OWNER
- EXISTING VCT AND BASE TO REMAIN OPTION 1: PROVIDE OPTION TO GRIND (E) CONCRETE AND INSTALL CERAMIC
- TILE FLOORING W/ 6" COVED BASE, SCHLUTER SS TRANSITION AT DOOR 4. OPTION 2: PROVIDE OPTION TO POLISH (E) CONCRETE FLOORING IN LIEU OF
- 5. OPTION 3: PROVIDE OPTION FOR CERAMIC TILE WAINSCOT TO 4'-0" AFF IN LIEU OF FRP (DEMO (E) GWB AND INSTALL CEMENT BOARD OR BLUE BOARD AT TILE AREAS)

TILE OR LVT

- PRIME & PAINT ALL SIDES OF EXPOSED WOOD FINISHES
- 2. UNLESS OTHERWISE NOTED, PROVIDE 4" BLACK VINYL COVE BASE AT ALL
- WALLS TO RECEIVE GWB FINISH 3. ALL HM DOOR TRIM TO BE PAINTED BLACK SEMI-GLOSS

CHANGE IN LEVEL REQUIREMENTS).

4. PROVIDE SCHLUTER SCHIENE TRANSITION STRIPS, 304 STAINLESS STEEL FINISH, AT ALL SAME-HEIGHT MATERIAL TRANSITIONS AND TERMINATIONS, PROVIDE SLOPED TRANSITIONS, 304 STAINLESS STEEL FINISH, WHERE CHANGE IN LEVEL IS REQUIRED (REFER TO SHEET T02 FOR THRESHOLD &

> (530) 344-4073 LANNING REVIEW BY

> > CITY OF FRESNO DARM DEPT

KM Architecture, Inc.

A Full Service Architectural Practice

3420 COACH LANE, SUITE 9.

CAMERON PARK, CA,

EMBARC, FRESNO TENANT IMPROVEMENTS

7363 N. BLACKSTONE AVE PINEDALE, CA 93650

CONSTRUCTION DOCUMENTS

30305316

KIRK MILLER Project Architect his drawing is not final, or to be used for construc until the Architect's or Engineer's seal and signatur

FLOOR PLAN

3/22/23 CUP COMMENTS DATE MARK DESCRIPTION

(C) KM Architecture, Inc. 2022 All Rights Reserved

